

Haryana Government Gazette EXTRAORDINARY

Published by Authority

© Govt. of Haryana

No. 76-2020/Ext.] CHANDIGARH, WEDNESDAY, JUNE 3, 2020 (JYAISTHA 13, 1942 SAKA)

हरियाणा सरकार

नगर तथा ग्राम आयोजना विभाग

तथा

शहरी स्थानीय निकाय विभाग

अधिसूचना

दिनांक 3 जून, 2020

संख्या सीसीपी(एनसीआर)/एफडीपी/एसबीडी/2020/494.— हरियाणा नगरपालिका अधिनियम, 1973 (1973 का 24) की धारा 203 ग की उपधारा (7) तथा पंजाब अनुसूचित सड़क तथा नियंत्रित क्षेत्र अनियमित विकास निर्बन्धन अधिनियम, 1963 (1963 का पंजाब अधिनियम 41), की धारा 5 की उप—धारा (7) तथा हरियाणा सरकार, शहरी स्थानीय निकाय विभाग तथा नगर तथा ग्राम आयोजना विभाग, अधिसूचना संख्या सी.सी.पी. (एन.सी.आर)/153/2019/1848, दिनांक 13 सितम्बर, 2019 के प्रतिनिर्देश से, हरियाणा के राज्यपाल, इसके द्वारा, शाहबाद नियन्त्रित क्षेत्र, अतिरिक्त नियन्त्रित क्षेत्र शाहबाद, राष्ट्रीय राजमार्ग संख्या—44 (पूर्व राष्ट्रीय राजमार्ग संख्या 1) के साथ—साथ नियन्त्रित क्षेत्र पॉकेट I तथा पॉकेट II के लिए अनुबन्ध 'ख' में विनिर्दिष्ट नियंत्रित क्षेत्रों को लागू तथा अनुबन्ध 'क' तथा 'ख' में दिए गए निर्बन्धनों तथा शर्तों सिहत शाहबाद की अंतिम विकास योजना 2031 ईस्वी प्रकाशित करते हैं।

ड्राईंग

- 1. विद्यमान भूमि उपयोग योजना ड्राईंग संख्या डीटीपी (केकेआर) 741/2000, दिनांक 26 मई, 2000. हरियाणा सरकार, नगर तथा ग्राम आयोजना विभाग, अधिसूचना संख्या सीसीपी(एनसीआर)/डीडीपी/(एसबीडी)/2008/769, दिनांक 14 मार्च, 2008 द्वारा पहले से प्रकाशित।
- 2. विद्यमान भूमि उपयोग योजना ड्राईंग संख्या डीटीपी (केके) 964/2010, दिनांक 11 अगस्त, 2010 (हरियाणा सरकार, शहरी स्थानीय निकाय विभाग तथा नगर तथा ग्राम आयोजना विभाग, अधिसूचना सी.सी.पी. (एन.सी. आर)/153/2019/1848, दिनांक 13 सितम्बर, 2019 द्वारा पहले से प्रकाशित।)
- 3. विद्यमान भूमि उपयोग योजना ड्राईंग संख्या डीटीपी (केके) 965/2010, दिनांक 20 अगस्त, 2010 (हरियाणा सरकार, शहरी स्थानीय निकाय विभाग तथा नगर तथा ग्राम आयोजना विभाग, अधिसूचना संख्या सी.सी.पी. (एन.सी. आर)/153/2019/1848, दिनांक 13 सितम्बर, 2019 द्वारा पहले से प्रकाशित।) ।
- 4. अंतिम विकास योजना ड्राईंग संख्या डीटीपी (के के) 1160 / 2019, दिनांक 12 अक्तूबर, 2019 ।

अनुबन्ध-क

अंतिम विकास योजना–2031 ईस्वी शाहबाद पर व्याख्यात्मक टिप्पण।

I परिचय :–

शाहबाद कस्बा तरावड़ी की लडाई के बाद 1192 ई. में शाहाबुद्वीन गौरी के अनुयायियों द्वारा बसाया गया था। यह एक उप—मण्डल है। इसके उतर में मारकण्डा नदी तथा पश्चिम में दिल्ली—अमृतसर रेलवे लाईन, मुख्य भौतिक अवरोधक है। पूर्व में नई अनाज मण्डी तथा चीनी मिल तथा दक्षिण में शहरी सम्पदा तथा अन्य संस्थानों का होना स्पष्ट रूप से इन दोनों दिशाओं में विकास होना दर्शाता है। राष्ट्रीय राजमार्ग संख्या—44 (पूर्व राष्ट्रीय राजमार्ग संख्या 1) पर होने के कारण इस क्षेत्र में विशाल सामाजिक—आर्थिक तथा भौतिक विकास हुआ है। शाहबाद कस्बे की जनसंख्या में बढ़ोतरी के परिणामस्वरूप तथा अवसंरचना की उपलब्धता जैसे जल, विद्युत, सड़क तन्त्र, संचार तथा दूरसंचार शहरी सम्पदा को ध्यान में रखते हुए शाहबाद कस्बे में नई शहरी सम्पदा का नियोजन किया गया। यहां सभी धर्मों के लोग रहते हैं।

शाहबाद करबा 30°10' उत्तर अक्षांश तथा 76°52' पूर्वी देशान्तर पर स्थित है। इस शहर में औद्योगिक गतिविधियाँ मूल रूप से कृषि से सम्बन्धित हैं। जैसे ही नियन्त्रित क्षेत्र में नगर के समीप नगर∕शहरी केन्द्र का विकास होगा तो दृश्य—विधान मूलतः परिवर्तित होगा। बांध तथा रेलवे लाईन शहर को मारकण्डा नदी की बाढ़ से बचाते हैं।

यह सारा क्षेत्र मैदानी है। बरसाती पानी दक्षिण—पश्चिम की ओर बहता है। इस क्षेत्र की भूमि उपजाऊ है तथा भूजल तल लगभग 240 फुट पर है। पानी पीनेयोग्य तथा बहुत मीठा है।

II जनसांख्यिकी रेखाचित्र:-

शाहबाद कस्बा की विद्यमान आबादी नगरपालिका सीमा में पड़ती है। इसकी आबादी 2011 में 42607 व्यक्ति थी। 1961—1971 के दौरान जनसंख्या की दशकीय वृद्धि दर 13.3 प्रतिशत थी, जो 1971—1981 में बढ़कर 22.36 प्रतिशत हो गई है। यद्यपि 1981—1991 में 19.55 प्रतिशत, 1991—2001 में 18.00 प्रतिशत तथा 2001—2011 में 19.55 प्रतिशत की कमी हुई है। जैसा नीचे दर्शाया गया है:—

वर्ष	जनसंख्या	दशकीय प्रतिशतता
1951	17,301	-
1961	18,975	9.6%
1971	21,500	13.3%
1981	26,308	22.36%
1991	31,452	19.55%
2001	37,130	18.00%
2011	42,607+3018* =45625	22.88%

^{*} शहरीकृत क्षेत्र में पड़ने वाले गाँवों की आबादी

III आर्थिक विशेषताएं :-

इस नियंत्रित क्षेत्र में पड़ने वाले कस्बे तथा अन्य गावों का आर्थिक आधार मुख्य रूप से कृषि है। मुख्य उगाई जाने वाली फसले गेंहू, चावल, गन्ना तथा मक्की हैं। लोगों की दैनिक आवश्यकताओं को पूरा करने के लिए कुछ परचून दुकानें, वाणिज्यिक केन्द्र तथा अनाज मण्डी विद्यमान हैं। इसके अतिरिक्त, इस क्षेत्र में लघु उद्योग जैसे कोल्ड स्टोर, राईस शैलर, फ्लोर मिल तथा मुख्य उद्योग जैसे शुगर मिल, वनस्पति मिल, फर्टिलाईजर मिल स्थापित है।

IV पर्यावरण के परिपेक्ष में भूमि उपयोग का विद्यमान वितरण, सेवाएं, जन उपयोगिताएं, सुविधाएं:--

(क) उपयोगिताएं:-

- (i) रिहायशी अंचल के अन्तर्गत 105 हैक्टेयर क्षेत्र 373 व्यक्ति प्रति हैक्टेयर के घनत्व से है।
- (ii) वाणिज्य, परचून तथा थोक व्यापार, पर्यटन सेवा क्षेत्र/भीतरी प्रदेश तथा विरासत के अन्तर्गत 64 हैक्टेयर है। लोगों की दैनिक जरूरतों को पूरा करने के लिये परचून की काफी दुकानें, वाणिज्य केन्द्र तथा एक अनाज मण्डी विद्यमान है इसलिए शहर वाणिज्यिक गतिविधियों में तेजी से उभर रहा है।
- (iii) ओद्योगिक क्षेत्र के अधीन 60 हैक्टेयर क्षेत्र पड़ता है। अधिकतर उद्योग राष्ट्रीय राजमार्ग संख्या 44 तथा साहा से शाहबाद जाने वाले (अनुसूचित सड़क संख्या 78) पर विद्यमान है।

- (iv) शाहबाद कस्बा राष्ट्रीय राजमार्ग संख्या 44 तथा बरोडगेज विद्युत रेलवे लाईन पर अवस्थित है। राष्ट्रीय राजमार्ग संख्या 44 पर कमशः रेलवे स्टेशन तथा बस स्टैण्ड विद्यमान है। इस प्रकार यह क्षेत्र राज्य के अन्य महत्वपूर्ण शहरों से अच्छी प्रकार जुड़ा हुआ है। कस्बे के अन्दर सड़कें/गिलयां आमतौर पर तंग है जो कि 6 मीटर से लेकर 14 मीटर तक चौड़ी है। शहर में एक टेलीफोन एक्सचेंज पहले से ही कार्यशील है। यहां पर वाहन सड़क के किनारे खड़े किये जाते हैं। परिवहन तथा संचार अंचल के अन्तर्गत 71 हैक्टेयर क्षेत्र पड़ता है।
- (v) वर्तमान में बिजली की आपूर्ति 66 के वी उपकेन्द्र से की जा रही है जो कि राष्ट्रीय राजमार्ग संख्या 44 पर स्थित है, जो वर्तमान की जरूरतों को पूरा करता है। जल की अपूर्ति जन स्वास्थ्य विभाग द्वारा स्थापित नलकूपों से की जाती है। शहरी सम्पदा में भी मल निकास प्रणाली पहले ही बिछाई गई है। कस्बा आबादी में खुली नालियां गलियों के साथ-साथ निर्मित की गई हैं। जन उपयोगिता अंचल के अन्तर्गत 10 हैक्टयेर क्षेत्र पडता है।

(ख) सामाजिक अवसंरचना :--

- (i) शैक्षणिक सुविधाएं उपलब्ध करवाने हेतु तीन डिग्री कालेज, तीन सीनियर सैकण्डरी स्कूल, हाई स्कूल, प्राइमरी स्कूल तथा नर्सरी स्कूल हैं। यहां एक विश्वविद्यालय (आदेश हरियाणा विश्वविद्यालय), एक 70 बिस्तर वाला अस्पताल, कई निजी नर्सिंग होम, क्लीनिक तथा एक पशु चिकित्सालय है। कस्बे में सामाजिक एकत्रीकरण के प्रयोजन के लिए धर्मशालाएं हैं। यहां पर मारकण्डेश्वर मन्दिर, देवी बाला सुन्दरी मन्दिर तथा शाकुम्भरी देवी मन्दिर है। सार्वजनिक तथा अर्ध सार्वजनिक अंचल के अधीन 36 हैक्टेयर क्षेत्र पडता है।
- (ii) यहां पर मुख्यतः चौधरी रणबीर सिंह हुडा के नाम से पार्क है। कस्बे में एक स्टेडियम हैं। यहां पर दो शमशान घाट / शवदाह गृह हैं। कस्बे में खुले स्थानों तथा पार्कों की कमी है। खुले स्थानों के अधीन 28 हैक्टेयर क्षेत्र पड़ता है।

V नियन्त्रित क्षेत्र घोषित करने की आवश्यकता :-

शहर की शहरी वृद्धि को ध्यान में रखते हुए, पंजाब अनुसूचित सड़क तथा नियंत्रित क्षेत्र अनियमित विकास निर्बन्धन अधिनियम 1963 (1963 का पंजाब अधिनियम 41) की धारा—4 की उपधारा (1) के खण्ड—(क) के अधीन हरियाणा सरकार, नगर तथा ग्राम आयोजना विभाग अधिसूचना संख्या 8028 वीडीपी—70/6784, दिनांक 17 दिसम्बर, 1970 द्वारा नियन्त्रित क्षेत्र घोषित हुआ तथा जिसका प्रकाशन हरियाणा राजपत्र में 29 जून, 1971 को हुआ। इस क्षेत्र की विकास योजना का प्रकाशन जनवरी, 1973 में हुआ था। चीनी मिल, तहसील कार्यालय, महाविद्यालय तथा नई अनाज मण्डी आदि की स्थापना के कारण हरियाणा सरकार राजपत्र दिनांक 18 सितम्बर, 1998 के प्रकाशित अधिसूचना संख्या सी. सी. पी.(एन. सी. आर)/केकेआर सीए—2/1620, दिनांक, 18 सितम्बर, 1998 द्वारा अतिरिक्त नियन्त्रित क्षेत्र घोषित किया गया था। इसके अतिरिक्त, नियन्त्रित क्षेत्र पॉकेट—I तथा II राष्ट्रीय राजमार्ग संख्या—44 के साथ—साथ 7 दिसम्बर, 2009 को प्रकाशित अधिसूचना संख्या सी.सीपी. /केकेआर/सीए—एएलएनजी, एनएच—1/2009/3339 दिनांक 7 दिसम्बर, 2009 द्वारा घोषित किया गया था।

VI योजना प्रस्तावनाएं:--

जनसंख्या प्रक्षेपणः मारकण्डा नदी शाहबाद करबा के उत्तर पश्चिम की तरफ से नियंत्रित क्षेत्र के मध्य से गुजरती है। यह नदी प्रस्तावित योजनाबद्ध विकास के लिए प्राकृतिक अवरोध है। वर्तमान करबा में भविष्य में विकास के सम्बन्ध में अधिक सम्भावना है। प्रस्तावना का कुल नियन्त्रित क्षेत्र 14271 हैक्टेयर क्षेत्र है, जिसमें से 1116 हैक्टेयर क्षेत्र शहरीकरण प्रयोजनों के लिए प्रस्तावित किया गया है।

कस्बा की जनसंख्या की वृद्धि दर सन्तुलित है। भविष्य में जनसंख्या प्रक्षेपण, 2011–2021 तथा 2021–2031 दशकों के लिए 40 प्रतिशत औसत वृद्धि दर किया गया है जोकि कमशः 82000 तथा 1,46,000 व्यक्तियों का बनता है। विद्यमान क्षेत्र तथा रिहायशी क्षेत्र की अधिक मांग को ध्यान में रखते हुए तथा 253 व्यक्ति प्रति हैक्टेयर घनत्व को ध्यान में रखते हुए रिहायशी क्षेत्र 105 + 470 = 575 हैक्टेयर में 1,46,000 की जनसंख्या को इस योजना में समायोजित करना प्रस्तावित किया गया है। जैसा कि नीचे दर्शाया गया है:–

तालिका–I

वर्ष	जनसंख्या	दशकीय प्रतिशतता
2021	82,000	79.73%
2031	1,46,000	78.05%

भि उपयोग:-

1116 हैक्टेयर का क्षेत्र, 96 व्यक्ति प्रति हैक्टेयर के कुल घनत्व से शहरी क्षेत्र के रूप में रखा गया है। शहर में विभिन्न सामाजिक—आर्थिक गतिविधियों की अपेक्षाओं को पूरा करने हेतु परिप्रेक्ष्य वर्ष 2031ईस्वी के लिए लगभग 1,46,000 व्यक्तियों की प्रक्षेपित जनसंख्या सिहत शहर को योजनाबद्ध किया गया है, शहर को जोड़ने की प्रकृति को ध्यान में रखते हुए विभिन्न भूमि उपयोगों के लिए भूमि युक्तिपूर्वक चिहिनत की गई है। नियंत्रित क्षेत्र में प्रस्तावित भूमि उपयोग के विस्तृत ब्यौरा निम्न प्रकार है:—

तालिका –॥

(हैक्टेयरमें क्षेत्र)

						(एप८परन यार
क्रम संख्या	भूमि उपयोग	नगर पालिका की सीमा के भीतर का क्षेत्र	नगर पालिका की बढ़ी हुई सीमा के भीतर का क्षेत्र	नियंत्रित क्षेत्र के भीतर क्षेत्र	कुल क्षेत्र	कुल क्षेत्र की प्रतिशतता
1	रिहायशी		444	60	504	45.16
2	वाणिज्यिक		124	00	124	11.12
3	औद्योगिक		48	48	96	8.60
4	परिवहन तथा संचार		97	46	143	12.81
5	सार्वजनिक उपयोग		12	15	27	2.42
6	सार्वजनिक तथा अर्ध – सार्वजनिक		41	00	41	3.67
7	खुले स्थान / हरित पटटी		133	30	163	14.61
8	विशेष अंचल		18	00	18	1.61
	कुल		917	199	1116	100.00

टिप्पण: {कुल शहरी क्षेत्र = 1490 हैक्टेयर अर्थात् 1116 हैक्टेयर (योजनाबद्ध शहरीकरण क्षेत्र + 374 हैक्टेयर (वर्तमान शहर के अधीन क्षेत्र)}

कुल नियन्त्रित क्षेत्र शाहबाद = 14271 हैक्टेयर

भूमि उपयोगों का विवरण:-

1. रिहायशी क्षेत्र :-

1,46,000 व्यक्तियों की प्रक्षेपित जनसंख्या को 2031 ईस्वी तक समायोजित करने के लिए रिहायशी क्षेत्र हेतु 504 हैक्टेयर भूमि आरक्षित की गई है । रिहायशी सेक्टर संख्या 1 (भाग), 3(भाग), 5, 6, 9 (भाग), 10(भाग), 13 तथा 14(भाग) प्रस्तावित किया गया है। प्रत्येक रिहायशी ड्राईंग में दर्शाई गई सेक्टर सघनता तथा इसके अतिरिक्त नई एकीकृत अनुज्ञापन पॉलिसी (एनआईएलपी), अफोर्डेएबल ग्रुप हाऊसिंग पॉलिसी, दीन दयाल जन आवास योजना पॉलिसी (डीडीजेएवाई) में यथा विहित सघनता में विकसित किया जाएगा। 20 प्रतिशत ग्रुप हाऊसिंग कम्पोनेन्ट पॉलिसी रिहायशी सेक्टर में भी लागू होगी।

उपरोक्त के अलावा, विकास योजना में निम्नलिखित प्रावधान भी किए गए हैं :-

- क. अवसंरचना के लिए अतिरिक्त क्षेत्र अतिरिक्त जनसंख्या की मांग को पूरा करने के लिए पहले ही योजनाबद्ध / विकसित आवासीय सेक्टरों में मुहैया करवाया जाएगा।
- ख. आवासीय कॉलोनी / सेक्टर में सड़कों की कम से कम चौड़ाई 12 मीटर से कम नहीं होगी या संबंधित नीति के अनुसार होगी।
- ग. आवासीय कॉलोनी/सेक्टर में पार्की/खुले स्थानों के लिए न्यूनतम क्षेत्र ऐसी रीति में योजनाबद्ध किया जाएगा जो 2.50 वर्गमीटर प्रति व्यक्ति के न्युनतम मानक को पुरा करेगा।

2. वाणिज्यिक :--

शहर में बहुत ही उपजाऊ कृषि भूमि होने के कारण भीतरी प्रदेश स्थानीय वाणिज्यिक केन्द्र के रूप में उभर रहा है। वाणिज्यिक उद्देश्यों के लिए 124 हैक्टेयर भूमि का क्षेत्र सेक्टर 3(भाग), 9(भाग), 12, तथा 14(भाग)में चिहिनत किया गया है।

3. औद्योगिक:-

इस क्षेत्र में मुख्य विकासशील उद्योग चावल शैलर है। इस उद्योग को चलाने के लिए बड़े पैमाने की भूमि की आवश्यकता है। इस प्रकार इनको शहर के बाहर/शहरीकृत क्षेत्र से बाहर स्थापित किया गया है। इस प्रकार की कृषि आधारित उद्योगों को ध्यान में रखते हुए अनुबन्ध—ख में उपयुक्त प्रावधान किए गए हैं। भीतरी प्रदेश के साथ विपणन सुविधाएं उपलब्ध करवाने हेतु कृषि आधारित/खाद्य प्रसंस्करण उद्योग के विकसित होने के लिए काफी अवसर हैं। इसलिए औद्योगिक गतिविधियों को उन्नत करने के लिए उपयोग के लिए सेक्टर 7(भाग), 8 तथा 11(भाग) 96 हैक्टेयर भूमि चिहिनत की गई है। शहर में हवाएं उत्तर—पश्चिम से दक्षिण—पूर्व दिशा की ओर चलती हैं। शहर में शुगर मिल पहले से ही स्थापित है।

परिवहन तथा संचार:—

राष्ट्रीय राजमार्ग संख्या—44 तथा लाडवा अनुसूचित सडक संख्या 69, अनुसूचित सड़क संख्या 57 काला अम्ब, सढौरा—शाहाबाद—ठोल सड़क करबे से गुजरते हैं। शहर से गुजरने वाली सभी अनुसूचित सड़कों के दोनों ओर 30 मीटर चौड़ी हरित पट्टी को प्रस्तावित किया गया है जबिक शहरीकरण के 1116 हैक्टेयर क्षेत्र प्रस्तावित किया गया है। सेक्टर विभाजन के लिए 45 मीटर चौड़ी सड़क का प्रस्ताव किया गया है। वी—3 सड़क के साथ 30 मीटर हरित पट्टी की प्रस्तावना की गई है। पैरिफरियल सड़क को 45 मीटर चौड़ाई के साथ 30 मीटर हरित पट्टी के रूप में प्रस्तावना की गई है। परिवहन तथा संचार अंचल के अधीन 143 हैक्टेयर भूमि प्रस्तावित की गई है जिसमें सड़कों के अधीन लगभग 62 हैक्टेयर का क्षेत्र भी आता है तथा 81 हैक्टेयर का क्षेत्र सेक्टर—4 तथा 11(भाग) में चिहिनत गया है। प्रस्तावित योजना में विभिन्न सड़कों के साथ भूमि आरक्षित की गई है जिसका विवरण निम्न प्रकार से है:—

क्रम संख्या	वर्गीकरण	भूमि आरक्षण
(i)	वी—1 संख्या	दोनों ओर 30 मीटर चौड़ी हरित पट्टी के साथ वर्तमान चौड़ी
	राष्ट्रीय राजमार्ग संख्या 44 (पूर्व राष्ट्रीय राज मार्ग संख्या–1)	
(ii)	वी –1 (ए) सड़क	दोनों तरफ 30 मीटर चौड़ी हरित पट्टी के साथ 45 मीटर चौड़ी पैरीफेरिल सडक
(iii)	वी —1 (बी) सड़क	प्रस्तावित सैक्टर सड़क 45 मीटर चौड़ी
(iv)	वी —2 सड़क	दोनों तरफ 30 मीटर चौड़ी हरित पट्टी के साथ अनुसूचित सड़कें
(v)	वी —3 सड़क	30 मीटर चौड़ी प्रस्तावित सेक्टर सड़क
(vi)	वी —4 सड़क	विद्यमान सेक्टर सड़क 30 मीटर चौड़ी ।

5. जन उपयोगिताएं :--

जन उपयोगिताओं अंचल के लिए 27 हैक्टेयर क्षेत्र चिहिनत किया गया है,जिसमें मल निस्तारण कार्य, ठोस कचरे के निपटान तथा शहर की अतिरिक्त आवश्यकताओं के पूर्ति हेतु विद्युत शक्ति संस्थापनाओं के लिए स्थान शामिल है।

सार्वजनिक तथा अर्ध—सार्वजनिक उपयोग :—

शैक्षणिक, सांस्कृतिक, धार्मिक, संस्थागत, चिकित्सा तथा स्वास्थ्य सुविधाएं उपलब्ध करने के लिए, 41 हैक्टेयर का क्षेत्र सैक्टर–2(भाग) तथा 10 (भाग) में आरक्षित किया गया है। सैक्टर 10 (भाग) में महाविद्यालय, अस्पताल, कामकाजी महिला होस्टल तथा वृद्धाश्रम प्रस्तावित किये गये है।

7. खुले स्थान तथा हरित पट्टी अंचल :--

वर्तमान राष्ट्रीय राजमार्ग संख्या—44 के दोनों ओर 30 मीटर चौड़ी हरित पट्टी प्रस्तावित है। इस हरित पट्टी तथा खुले स्थानों के अधीन 163 हैक्टेयर का क्षेत्र पड़ता है। प्रस्तावित पैरिफेरियल सड़क के दोनों ओर 30 मीटर चौड़ी हरित पट्टी प्रस्तावित की गई है।

कृषि अंचल :

शहरीकरण प्रस्तावों के आसपास बाकी का क्षेत्र जो कि प्रमुख रुप से कृषि योग्य है, कृषि अचंल के रुप में आरक्षित किया जाना प्रस्तावित है। तथापि, कृषि अंचल, इस क्षेत्र में अनिवार्य भवन कार्यकलापों को नहीं रोकेगा जैसे आबादी—देह से संलग्न मौजूदा गांव का विस्तार, यदि इस ग्रामीण क्षेत्र के रखरखाव तथा सुधार के लिए सहायक आवश्यक, सुविधाएं तथा सरकार द्वारा अनुमोदित या प्रायोजित परियोजना के अधीन लिया गया है।

9. विशेष अंचल :-

शहर की राष्ट्रीय राजमार्ग संख्या—44 पर अवस्थित होने के कारण, सेक्टर—2 (भाग) में, आमोद—प्रमोद, मनोरंजन तथा वाणिज्यिक गतिविधियों (मिश्रित भूमि उपयोग) हेतु 18 हैक्टेयर का क्षेत्र आरक्षित किया गया है।

अंचल विनियम :

भूमि उपयोग सम्बन्धी प्रस्तावों को अंचल विनियम (अनुबन्ध ख) बनाते हुए वैध बनाया जा रहा है जो इस विकास योजना का हिस्सा होंगे। ये विनियम भूमि उपयोग में परिवर्तन और विकास के मानकों को शासित करेंगे। इनमें सम्बद्ध तथा सहायक उपयोगों का भी विस्तारपूर्वक वर्णन किया जाएगा जो विभिन्न मुख्य भूमि उपयोगों में अनुमत किए जाएंगे तथा नियतन करेंगे कि भूमि उपयोग के सभी परिवर्तन तथा विकास, विकास तथा उचित नियन्त्रण के मार्गदर्शन के लिए प्रत्येक क्षेत्र के लिए विस्तृत सेक्टर योजनाएं तैयार करना सुनिश्चित करते हुए सेक्टर योजना में दर्शाए गए ब्यौरों के अनुसार होगा।

अनुबन्ध—ख

ड्राईंग संख्या डीटीपी(केके) 1160 / 2019, दिनांक 12.10.2019 में दर्शाए अनुसार शाहबाद के इर्दगिर्द नियंत्रित क्षेत्रों में भूमि के उपयोग तथा विकास को शासित करना।

I. सामान्यः-

- 1. शाहबाद के इर्दिगर्द नियंत्रित क्षेत्रों के लिए अंतिम विकास योजना का भाग रूप बनने वाले इन अंचल विनियमों को, नियंत्रित क्षेत्र शाहबाद के लिए अंतिम विकास योजना के अंचल विनियम कहा जायेगा।
- 2. इन विनियमों की अपेक्षाएं, अंतिम विकास योजना में शामिल समूचे क्षेत्र की सीमा तक होंगी तथा हरियाणा नगरपालिका अधिनियम, 1973 (1973 का 24) तथा पंजाब अनुसूचित सड़क तथा नियंत्रित क्षेत्र अनियमित विकास निर्बन्धन अधिनियम, 1963 (1963 का पंजाब अधिनियम 41) और उसके अधीन बनाये गये नियमों की अपेक्षाओं के अतिरिक्त होंगी।

II. परिभाषायें :-

इन विनियमों में,-

- (क) 'कृषि आधारित उद्योग' से अभिप्राय है, ऐसी औद्योगिक इकाई, जो खाद्यान्न, फलों या कृषि अपशिष्ट का उपयोग कच्चे माल के रूप में करती है:
- (ख) 'अनुमोदित' से अभिप्राय है, सक्षम प्राधिकारी द्वारा अनुमोदित;
- (ग) 'भवन संहिता' से अभिप्राय है, हरियाणा भवन संहिता, 2017;
- (घ) 'भवन नियमों' से अभिप्राय है, नियमों के भाग-VII में अन्तर्विष्ट नियम;
- (ड.) 'साईबर सिटी' से अभिप्राय है, केन्द्रकीय सूचना प्रौद्योगिकी परिकल्पना के लिए विकसित और कम्पनियों सूचना प्रौद्योगिकी आधारित सेवाओं के मध्यम तथा बड़े साफ्टवेयर उत्पन्न किए जाने के लिए अति उच्चतम गुणवत्ता का मूलभूत ढांचा, उत्तम परिस्थितियां और उच्च गित संचार से आत्मिनर्भर परिपूर्ण शहर, जहां विनिर्माण ईकाईयों को अनुमत नहीं किया जाएगा;
- (च) 'साईबर पार्क/सूचना प्रौद्योगिकी पार्क' से अभिप्राय है, वह क्षेत्र जो केवल साफ्टवेयर विकास सम्बन्धी क्रिया कलापों का पता लगाने तथा सूचना प्रौद्योगिकी को समर्थ बनाने वाली सेवाओं के लिए विकसित हों, इसमें किसी भी प्रकार के विनिर्माण (असैम्बलिंग क्रियाकलापों सहित) की अनुमति प्रदान नहीं की जाएगी;
- (छ) 'ज़ाईंग' से अभिप्राय है, ड्राईंग संख्या डीटीपी(केके) 1160 / 2019, दिनांक 12.10.2019;
- (ज) 'व्यापक उद्योग' से अभिप्राय है, ऐसा उद्योग जो सरकार की अनुमित से स्थापित किया जाये और जो व्यापक हो, जिसमें 100 से अधिक कामगार नियुक्त हों तथा जिसमें ईंधन चालित शक्ति का प्रयोग किया जाये बशर्ते कि इसमें किसी प्रकार के हानिकारक तत्व न हों;
- (झ) "फार्म गृह" से अभिप्राय है, किसी फार्म के स्वामी द्वारा अपनी भूमि पर निम्नलिखित प्रयोजनार्थ निर्मित घर है—
 - (i) निवास यूनिट अर्थात् मुख्य उपयोगः,
 - (ii) फार्म छायाबान अर्थात् गौण उपयोग।

टिप्पण:-

- (1) फार्म गृह का निर्माण 'कृषि अंचल में आबादी देह से बाहर फार्म गृहों की व्यवस्था' संबंधी खण्ड XIX के अधीन दिये गये निर्बन्धनों से शासित होगा;
- (2) 'फार्म शैड' 'भवन नियंत्रण और स्थल विशिष्टियां', के सम्बन्ध में खंड XIX में उल्लेखित निर्बन्धनों द्वारा शासित होंगे।

(ञ) **'फर्श क्षेत्र अनुपात'** से अभिप्राय है, सभी मंजिलों के कुल आच्छादित क्षेत्र तथा सौ के गुणक को प्लाट क्षेत्र से विभाजित करते हुए प्राप्त किया गया भागफल, अर्थात :--

फर्श क्षेत्र अनुपात की गणना के प्रयोजन के लिए, कैंटिलीवर अनुमत छत प्रोजेक्शनों; लिफ्ट कमरा, ममटी, छज्जा, तहखाना या कोई फर्श यदि पार्किंग, सेवाओं और मंडारण, केवल पार्किंग/पैदल यात्री प्लाजा के लिए उपयोग हेतु प्रस्तावित स्टिलट क्षेत्र, (खुला), खुली सीढ़ी (ममटी के बिना), पहुँच के साथ या के बिना, छत अग्नि सीढ़ी, अलिंद पानी की टंकी, अनुमत आकार के खुला आंगन के लिये उपयोग किया गया हैं, फर्श क्षेत्र अनुपात में गिना नहीं जाएगाः

परंतु स्टिलट से अगली मंजिल तक शाफ्ट, शूटस, लिफ्ट वैल तथा सीढ़ी के अधीन क्षेत्र, भूमि तल से फर्श क्षेत्र अनुपात केवल एक बार गिना जाएगाः

परंतु यह और कि यदि वेंटिलेशन शाफ्ट क्षेत्र 3 वर्ग मीटर से अधिक है, तो यह फर्श क्षेत्र अनुपात में नहीं गिना जाएगा:

- (ट) **'ईधन स्टेशन'** से अभिप्राय है, ईंधन भरने वाला स्टेशन जो ऑटोमोबाइल के लिए ईंधन की खुदरा आपूर्ति प्रदान करता है, जिसमें पेट्रोल पम्प, सी. एन. जी. स्टेशन, जैव–ईंधन, चार्जिंग स्टेशन, बैटरी उपलब्ध स्टेशन आदि शामिल हैं:
- (ठ) 'हरित पट्टी' से अभिप्राय है, विकास योजना में दर्शाए गए सेक्टर/परिधि सड़कों के साथ-साथ की भू पट्टी जो भविष्य में सड़क को चौड़ा करने के लिए उपयोग हो; तथा
- (ड) 'वर्ग आवास' से अभिप्राय है, रिहायशी प्रयोजन के लिए फ्लैटों के रूप में डिजाईन तथा विकसित किये गये भवन या वर्ग आवास का अनुषंगी कोई भवन;
- (ढ) 'भारी उद्योग' से अभिप्राय है, सरकार की अनुमित से सार्वजनिक या अर्ध—सार्वजनिक या निजी क्षेत्र में स्थापित किया गया उद्योग (प्लान्ट, मशीनरी इत्यादि की लागत जैसे कि सरकार की उद्योग नीति में परिभाषित हो);
- (ण) 'सूचना प्रौद्योगिकी औद्योगिक ईकाई' से अभिप्राय है, हरियाणा सरकार की सूचना प्रौद्योगिकी नीति, 2000 के अनुबन्ध में तथा इस अधिसूचना के परिशिष्ट—1 में शामिल उद्योगों की श्रेणियां तथा/ अथवा जो हरियाणा सरकार द्वारा, समय—समय पर परिभाषित की जाये;
- (त) 'टांड या पुश्तवान' से अभिप्राय है, कमरे के अन्दर बनाए गए अनुलम्ब खम्भे को छोड़कर, किसी भी स्वरूप की शैल्फ जैसे बहिर्गत भाग, बशर्ते जिसका बर्हिगत भाग एक मीटर से अधिक चौडा न हो।
- (थ) **'हल्के उद्योग'** से अभिप्राय है, ऐसा उद्योग जिसके कारण हानिकारक या घृणाजनक शोर, धुआं, गैस, भॉप गन्ध, धूल, बिहःस्राव और कोई अन्य अत्यधिक डिग्री का प्रदूषण न हो और बिजली द्वारा चालित हों;
- (द) 'स्थानीय सेवा उद्योग' से अभिप्राय है, ऐसा उद्योग जिसका विनिर्मित माल और उत्पादन प्रायः स्थानीय क्षेत्र के भीतर उपभोग किया जाता हो, उदाहरणार्थ बेकरियां, आईसक्रीम विनिर्माण, वातित जल, बिजली से चलने वाली आटे की चिक्कयां, लोंड्री, ड्राईक्लीनिंग और रंगाई, स्वचालित गाड़ियों, स्कूटर तथा साईकलों की मरम्मत तथा सर्विस, घरेलू बर्तनों की मरम्मत, जूते बनाना और उनकी मरम्मत, ईंधन डिपो आदि बशर्ते कि उनमें किसी ठोस ईंधन का प्रयोग न किया जाता हो;
- (ध) 'अटारी'से अभिप्राय है, अधिकतम 1.5 मीटर की ऊँचाई सहित अवशिष्ट स्थल पर दो मंजिलों के बीच का मध्यवर्ती स्थल तथा जो केवल मंडारण प्रयोजन हेतु निर्मित की गई है अथवा अपनाई गई है;
- (न) **'वास्तविक तिथि'** से अभिप्राय है, नीचे घोषित किए गए विभिन्न नियंत्रित क्षेत्रों की अधिसूचना के प्रकाशन की तिथि;

क्रम संख्या	<u> </u>	वास्तविक तिथि	
1.	हरियाणा राजपत्र में दिनांक २९ जून, १९७१ को प्रकाशित हरियाणा	१९ जुलाई, १९७१	
	सरकार, अधिसूचना संख्या ८०२८ वीडीपी–७०/६७८४ दिनांक १७.१२.१९७०	_	
	द्वारा अधिसूचित नियंत्रित क्षेत्र ।		
2.	हरियाणा राजपत्र में दिनांक 19 सितम्बर, 1998 को प्रकाशित हरियाणा	18 सितम्बर, 1998	
	सरकार, अधिसूचना संख्या सीसीपी (एनसीआर) / केकेआर–सीए–2 / 1620		
	द्वारा अधिसूचित नियंत्रित क्षेत्र।		
3.	हरियाणा राजपत्र में प्रकाशित हरियाणा सरकार, अधिसूचना संख्या सी.	7 दिसम्बर 2009	
	सीपी. / केकेआर / सीए–एएलएनजी, एनएच–1/ 2009 दिनांक 7		
	दिसम्बर, 2009 नियंत्रित क्षेत्र पॉकेट—I तथा II.		

- (प) 'मध्यम उद्योग' से अभिप्राय है, हल्का उद्योग तथा स्थानीय सेवा उद्योग के अलावा सभी उद्योग और जो घृणाजनक और खतरनाक गंध तथा दुर्गन्ध न फैलाते हों;
- (फ) 'परछती तल' से अभिप्राय है, निम्न मंजिल का 1/2 (आधा) तक के सीमित क्षेत्र सहित तथा न्यूनतम ऊँचाई 2. 3 मीटर सहित दो मंजिलों के बीच कोई मध्यवर्ती तल और ऊपरी तल स्तर से 2.3 मीटर (स्पष्ट ऊँचाई) से कम नहीं होगा:
- (ब) नियंत्रित क्षेत्र में किसी भूमि अथवा भवन के संबंध में 'अननुरूप उपयोग' से अभिप्राय है, ऐसी भूमि अथवा भवन जो विकास योजना में क्षेत्र के उस भाग के लिए विनिर्दिष्ट मुख्य भूमि उपयोग के विपरीत हो;
- (म) **'घृणाजनक या परिसंकटमय उद्योग'** से अभिप्राय है सरकार की अनुमित से स्थापित किया गया उद्योग और जिसमें अत्यधिक पूंजी लगी हो। जिसमें अत्यधिक धुंआ, शोर, स्पन्दन, दुर्गन्ध, अप्रिय या हानिकारक बिहःस्राव, विस्फोटक, ज्वलनशील सामग्री इत्यादि और समुदाय के स्वास्थ्य और सुरक्षा के लिए अन्य खतरनाक तत्व शामिल हों:
- (म) **'सार्वजनिक उपयोगिता सेवा भवन'** से अभिप्राय है, ऐसा भवन जो सार्वजनिक उपयोगिता सेवाओं को चलाने के लिए अपेक्षित हो, जैसे जल सप्लाई, जल निकास, बिजली, डाक तथा तार तथा परिवहन तथा दमकल केन्द्र सहित कोई नगरपालिका सेवा:
- (य) 'नियमों' से अभिप्राय है, पंजाब अनुसूचित सड़क तथा नियंत्रित क्षेत्र अनियमित विकास निर्बन्धन नियम, 1965;
- (य क) **सेक्टर क्षेत्र', और 'कॉलोनी क्षेत्र'** से अभिप्राय है, विकास योजना में ऐसे रूप में दर्शाये गये सेक्टर क्षेत्र या कॉलोनी क्षेत्र;

व्याख्या:-

- (1) इस परिभाषा में 'सेक्टर क्षेत्र' या 'कालोनी क्षेत्र' से अभिप्राय है, सेक्टर या कालोनी का क्षेत्र जो कालोनी/सेक्टर की अनुमोदित अभिन्यास योजना पर ड्राईंग में दर्शाया गया है जिसमें सेक्टर या कालोनी, जैसे भी स्थिति हो, में भवन विकास के लिए अनुपयुक्त क्षेत्र शामिल नहीं है;
- (2) मुख्य सड़कों तथा उनकी निकटवर्ती हरित पट्टी, यदि कोई हो, के अधीन आने वाले क्षेत्र का 50 प्रतिशत लाभ प्लाटिड / ग्रुप आवास कालोनी की दशा में प्लाटऐबल क्षेत्र / फर्श क्षेत्रफल अनुपात के लिए अनुज्ञात किया जायेगा;
- (3) औद्योगिक कालोनी / सेक्टर से भिन्न कालोनी या सेक्टर की विन्यास योजना में, सड़कों, खुले स्थानों, विद्यालयों, सार्वजनिक तथा सामुदायिक भवन तथा अन्य सामूहिक उपयोगों के लिए आरक्षित भूमि कालोनी / सेक्टर के अधीन भूमि के कुल क्षेत्र के 45 प्रतिशत से कम नहीं होगी।
- (4) सेक्टर संघनता या कालोनी संघनता की संगणना के प्रयोजनों के लिए यह माना जायेगा कि सेक्टर क्षेत्र या कालोनी क्षेत्र का 50 प्रतिशत आवासीय प्लाटों के लिए उपलब्ध होगा जिसमें ग्रुप आवास के अधीन क्षेत्र भी शामिल होगा तथा प्रत्येक भवन प्लाट औसतन प्रत्येक तीन निवास ईकाइयों में 4.5 व्यक्ति प्रति निवास ईकाई या 13.5 व्यक्ति भवन प्लाट या कालोनी / ग्रुप आवास समूह की अंचल योजना में यथा सम्मिलित होगा। यद्यपि, दुकान तथा आवासीय प्लाट के मामले में केवल एक निवास इकाई मानी जायेगी:
- (5) उपरोक्त दी गई किसी बात के होते हुए भी, विनिर्दिष्ट पॉलिसी जैसे नई एकीकृत अनुज्ञापन पॉलिसी के अधीन अनुमोदित परियोजनाएं; प्लॉटऐबल क्षेत्र की बजाय फर्श क्षेत्र अनुपात तथा सघनता पैरामीटर से शासित होंगी;
- (य ख) 'सेक्टर सघनता' और 'कॉलोनी सघनता', से अभिप्राय है, उस सेक्टर क्षेत्र तथा कॉलोनी क्षेत्र, जैसी भी स्थिति हो, में प्रति व्यक्तियों की संख्या;
- (य ग) 'स्थल आच्छादन' से अभिप्राय है, भवन के भूतल क्षेत्र और स्थल क्षेत्र द्वारा आच्छादित क्षेत्र के बीच प्रतिशतता में अभिव्यक्त अनुपात;
- (य घ) 'लघु उद्योग' से अभिप्राय है, ऐसी औद्योगिक इकाई जो उद्योग विभाग द्वारा लघु उद्योग के रूप में पंजीकृत हो;
- (य ड.) 'कृषि उपयोग साधन' से अभिप्राय है, ऐसा विकास तथा गतिविधियां, जो कृषि संबंधी कार्यों को करने में सहायक रूप में अपेक्षित है, जैसे कि नलकूप, पम्प, चैम्बर, वायु चक्की, सिंचाई, नाले, पक्के प्लेटफार्म, बाड़ लगाना तथा चारदीवारी बनाना, जल नलके आदि;
- (य च) 'अधिनियम', 'कालोनी', 'उप-निवेशक', 'विकास योजना', 'सेक्टर' और 'सेक्टर योजना' शब्दों का वही अर्थ होगा, जो उन्हें पंजाब अनुसूचित सड़क तथा नियंत्रित क्षेत्र अनियमित विकास निर्बन्धन अधिनियम, 1963 (1963 का पंजाब अधिनियम 41) में दिया गया है;
- (य छ) किन्हीं अन्य अभिव्यक्तियों का वही अर्थ होगा, जो उन्हें पंजाब अनुसूचित सड़क तथा नियंत्रित क्षेत्र, अनियमित विकास निर्बन्धन अधिनियम, 1963 (1963 का पंजाब अधिनियम 41) में दिया गया है।

III. मुख्य भूमि उपयोग / अंचल:-

- . (i) रिहायशी अंचल
 - (ii) वाणिज्यिक अंचल
 - (iii) औद्योगिक अंचल

- (iv) परिवहन तथा संचार अंचल
- (v) जन उपयोगिता अंचल
- (vi) सार्वजनिक तथा अर्धसार्वजनिक अंचल
- (vii) खुले स्थान अंचल
- (viii) कृषि अंचल
- (ix) विशेष अंचल
- 2. मुख्य भूमि उपयोगों का वर्गीकरण परिशिष्ट 'क' के अनुसार है।

IV. सेक्टरों में विभाजन:-

उपर्युक्त अंचल विनियमन—III में क्रम संख्या—(i) से (viii) पर वर्णित मुख्य भूमि उपयोग, जो भवन प्रयोजनार्थ भूमि उपयोग हैं, जिन्हें इन सेक्टरों की मुख्य सड़कों के आरक्षण हेतु दर्शाई गई हदबन्दी के अनुसार सेक्टरों में विभाजित किया गया है और प्रत्येक सेक्टर को ड्राईंग में दिखाये अनुसार एक निश्चित संख्या दी गई है।

V. मुख्य उपयोगों में भूमि उपयोग संबंधी ब्यौरे:-

मुख्य, सहायक तथा गौण उपयोग जो इन विनियमों तथा नियमों के अन्य अपेक्षाओं के अध्याधीन हैं, को मुख्य भूमि उपयोग अंचल में अनुमति दी जा सकती है, उनकी सूची परिशिष्ट ख पर दी गई है जो इन विनियमों के साथ जोड़े गये है।

VI. विकास के लिए अनुपयुक्त सेक्टर:-

विभिन्न सेक्टरों में भवन परियोजनार्थ, भूमि उपयोग के लिए आरक्षण होते हुए भी, निदेशक, नियंत्रित क्षेत्र के सघन तथा किफायती विकास के दृष्टिगत अपने भूमि उपयोग में किसी प्रकार के परिवर्तन के लिए अथवा उस पर किसी भवन के निर्माण के लिए ऐसे समय तक अनुमित नहीं देगा जब तक वह अपनी संतुष्टि सुनिश्चित नहीं कर लेता है कि इन सेक्टरों के लिए जल सप्लाई, जल मल निकास व्यवस्था तथा अन्य सुविधायें, उपलब्ध नहीं हो जाती हैं।

VII. केवल सरकारी उपक्रमों के माध्यम से विकसित किये जाने वाले सेक्टर :-

सरकार अपने द्वारा या उसके अभिकरणों द्वारा, विकास के लिए कोई सेक्टर अधिसूचित कर सकती हैं, ऐसे मामले में ऐसे सेक्टरों में भूमि उपयोग के परिवर्तन या अनुज्ञप्ति प्रदान करने के लिए आगे कोई भी अनुमति अनुमत नहीं की जाएगी ।

VIII. मुख्य सड़कों के लिए भूमि आरक्षण:-

(1) ड्राईग में चिहिनत की गई मुख्य सड़कों के लिए भूमि का आरक्षण निम्न प्रकार से किया जायेगा

क्रम संख्या	सड़कों का वर्गीकरण	भूमि आरक्षण
(i)	वी–1 राष्ट्रीय राजमार्ग संख्या 44	विद्यमान सड़क के दोनों तरफ 30 मीटर हरित पट्टी सहित।
(ii)	वी–1 (ए) सड़क	दोनों तरफ 30 मीटर सहित हरित पट्टी 45 मीटर चौड़ी बाहीय परिधीय सड़क ।
(iii)	वी—1 (ख) सड़क	45 मीटर चौड़ी सैक्टर सड़क।
(iv)	वी— 2 सड़क	दोनों तरफ 30 मीटर सहित निर्बन्धित पट्टी वर्तमान सड़क चौड़ाई ।
(v)	वी—3 सड़क	30 मीटर चौड़ी सैक्टर सड़क।
(vi)	वी—4 सड़क	30 मीटर वर्तमान चौड़ाई के साथ सैक्टर सड़क।

- (2) अन्य सड़कों की चौड़ाई और सीधाई, सेक्टर योजना के अनुसार अथवा कालोनियों की अनुमोदित अभिविन्यास योजना के अनुसार होगी।
- (3) व्यापारयोग्य फर्श क्षेत्र अनुपात का लाभ विनिर्दिष्ट पॉलिसी के अनुसार सेक्टर सड़क या हरित पट्टी तथा खुला क्षेत्र अंचलों के अधीन आने वाली भूमि के लिए प्रदान की गई अनुज्ञप्तियों के लिए अनुज्ञात किया जा सकता है।

IX. अननुरूप उपयोग अर्थात् विद्यमान या भूमि उपयोग में वैध परिवर्तन की अनुमित प्राप्त:-

 विकास योजना में औद्योगिक अंचल से भिन्न अंचलों में दर्शाए गए विद्यमान उद्योगों के संबंध में, निदेशक द्वारा निर्धारित की जाने वाली नियत अविध, किन्तु दस वर्ष से अधिक न हों, के लिए ऐसे औद्योगिक अननुरूप उपयोग जारी रखने की अनुमति दी जाएगी; बशर्ते कि सम्बद्ध भवन का स्वामी;

- (क) निदेशक को स्थल के बाह्य विकास के लिए, उस द्वारा यथानिर्धारित अनुपातिक प्रभारों तथा जब भी निदेशक द्वारा इस निमित्त ऐसा करने के लिए कहा जाये, के भुगतान का वचन देता है;
- (ख) अंतरिम अवधि के दौरान निदेशक की संतुष्टि के अनुसार बहिःस्राव के निष्कासन की सुनिश्चित व्यवस्था करेः तथाः
- (ग) अननुरूप उपयोग के क्षेत्र में विद्यमान परियोजना के विस्तार की अनुमति नहीं होगी ।
- 2. उन परियोजनाओं के बारे में, जिन्हें भूमि उपयोग की मान्य स्वीकृति है, तथा जो विकास योजना में अनुरूप उपयोग अंचल से भिन्न अवस्थित हैं, ऐसे अननुरूप उपयोग जारी रखने के लिए अनुमत किए जाएंगे, बशर्ते कि सम्बद्ध भवन का स्वामी:—
 - (क) निदेशक को स्थल के बाह्य विकास के लिए उस द्वारा यथा निर्धारित अनुपातिक प्रभारों तथा निदेशक द्वारा इस निमित्त ऐसा करने के लिए कहा जाये, के भुगतान का वचन देता है;
 - (ख) अंतरिम अवधि के दौरान निदेशक की संतुष्टि के अनुसार बिहः स्राव के लिए संतोषजनक व्यवस्था करे।

X. अननुरूप उपयोग बन्द करना:-

- (1) यदि किसी भूमि का अननुरूप उपयोग दो वर्ष या इससे अधिक अवधि के लिए लगातार बन्द रहा हो, तो उसे समाप्त हुआ समझा जायेगा और केवल अनुरूप अनुमत उपयोग के अनुसार ही भूमि के पुनःउपयोग या पुनःविकास की अनुमति दी जायेगी।
- (2) यदि अननुरूप उपयोग भवन, आग, बाढ़, विस्फोट, भूकम्प, लड़ाई, दंगा या किसी अन्य प्राकृतिक आपदा से इसके पुनरूत्पादन मूल्य के 50 प्रतिशत या इससे अधिक क्षतिग्रस्त हो जाता है, तो उसे केवल अनुमत उपयोग के लिए पुनःविकसित करने की अनुमित दी जायेगी।
- (3) खण्ड IX के अधीन शामिल परियोजनाओं के समाप्त होने के बाद, भूमि केवल अनुरूप उपयोग के लिए पुनः विकसित करने या उपयोग में लाने के लिए अनुमत की जायेगी।
- (4) खण्ड IX(1) के अधीन नियत अविध की समाप्ति के बाद, भूमि केवल अनुरूप उपयोग के लिए पुनः विकसित या उपयोग में लाने के लिए अनुमत की जाएगी।

XI. सेक्टर योजना और आंचलिक योजना के अनुरूप विकास:-

विनियम—IX में यथा उपबन्धित को छोड़कर, मुख्य भूमि उपयोग में किसी भी भूमि को भवन निर्माण प्रयोजनार्थ उपयोग तथा विकास के लिए तब तक अनुमत नहीं किया जाएगा जब तक प्रस्तावित उपयोग और विकास, सेक्टर योजना और आंचलिक योजना अथवा अनुमोदित कालोनी योजना, जिसमे भूमि अवस्थित है, में दिखाये गये ब्यौरे के अनुसार न हो।

XII. अनुमोदित अभिविन्यास या आंचलिक योजना का भाग बनने वाले विशिष्ट स्थल:-

किसी प्लाट पर भवन निर्माण या पुनःनिर्माण की अनुमति तब तक नहीं दी जायेगी जब तक –

- (i) प्लाट अनुमोदित कालोनी का भाग न हो या प्लाट ऐसे क्षेत्र में न हो, जिसके लिए विनियम XVIIमें यथा उपबन्धित अनुसार छूट दी गई है; तथा
- (ii) निदेशक की संतुष्टि अनुसार प्लाट तक पहुंच के लिए सड़क की व्यवस्था न हो और सड़क न बनी हो। XIII. विभिन्न प्रकार के भवनों के प्लाटों का न्यूनतम आकार:—

(1) विभिन्न प्रकार के उपयोगों के लिए प्लाटों के न्यूनतम आकार निम्न अनुसार होंगे:--

क्रम	भूमि उपयोग	_	आकार	
संख्या	-			
(i)	रिहायशी प्लाट	50 वर्ग मीटर	59.8 वर्ग	538.20 वर्ग
			गज	फीट
(ii)	सरकार द्वारा अनुमोदित आर्थिक सहायता प्राप्त	35 वर्ग मीटर	41.86 वर्ग	376.74 वर्ग
	औद्योगिक आवास या गन्दी बस्तियों में रहने		गज	फीट
	वालों के लिए आवास स्कीम में रिहायशी प्लाट			
(iii)	दुकान एवं रिहायशी प्लाट	100 वर्ग मीटर	119.60 वर्ग	1076.40 वर्ग
			गज	फीट
(iv)	शापिंग बूथ जिनमें सामने बरामदा या पत्थर तथा	20 वर्ग मीटर	23.92 वर्ग	215.28 वर्ग
	ईंट पैदल मार्ग शामिल हो		गज	फीट
(v)	स्थानीय सेवा उद्योग प्लाट	100 वर्ग मीटर	119.60 वर्ग	1076.40 वर्ग
			गज	फीट
(vi)	हल्के उद्योग प्लाट	250 वर्ग मीटर	299 वर्ग गज	2691 वर्ग
				फीट
(vii)	मध्यम उद्योग प्लाट	8000 वर्ग	9568 वर्ग	86112 वर्ग
		मीटर	गज	फीट

(2) रिहायशी और वाणिज्य विकास के लिये वर्ग आवास कालोनी, प्लाटिड रिहायशी कालोनी और वाणिज्य कालोनी के लिए क्षेत्र मानदण्ड समय—समय पर अधिसूचित नीतियों के अनुसार होंगे। तथापि, यदि वर्ग आवास स्कीम हरियाणा शहरी विकास प्राधिकरण या किसी अन्य सरकारी एजेंसी द्वारा जारी की जाती है, तो वर्ग आवास स्थल का आकार योजना में यथा विनिर्दिष्ट होगा।

XIV. विभिन्न प्रकार के भवनों के अन्तर्गत आच्छादित क्षेत्र, ऊँचाई और आकार:-

विशिष्ट प्लॉट/ स्थल पर अनुमत आच्छादित क्षेत्र, फर्श क्षेत्र अनुपात तथा ऊँचाई पैरामीटर, भवन संहिता/नियमों तथा/या ऐसे प्लाट/स्थल के जोनिंग प्लान में यथा अधिकथित विहित पॉलिसी द्वारा शासित होंगे।

XV. भवनों की अगली और पिछली ओर भवन पंक्त:-

ये भवन संहिता/नियमों के अनुसार तथा/या ऐसे क्षेत्र के जोनिंग प्लान में यथा अधिकथित उपबन्धित होगी।

XVI. वास्तुकला संबंधी नियंत्रण:-

जहां कहीं भी वास्तुकला संबंधी नियंत्रण आवश्यक समझा जाता है, तो प्रत्येक भवन, हरियाणा भवन संहिता, 2017 के खण्ड 6.4 के अधीन बनाये गए वास्तुकला संबंधी नियंत्रण के अनुरूप होगा।

XVII. कृषि अंचल में भूमि उपयोग में ढील:-

कृषि अंचल में आने वाली किसी भूमि के मामले में, सरकार इस विकास योजना के उपबन्धों में निम्नलिखित हेतु ढील दे सकती है,—

- (क) भूमि के आवासीय अथवा औद्योगिक कालोनी में उपयोग तथा विकास हेतु, बशर्तें उपनिवेशक द्वारा यह भूमि वास्तविक तिथि से पहले उक्त उपयोग तथा विकास के लिए क्रय की गई हो और उपनिवेशक नियमानुसार इस प्रयोजन के लिए अनुमित प्राप्त करता है।
- (ख) व्यक्तिगत स्थल के रूप में भूमि उपयोग हेतु (औद्योगिक कालोनी से भिन्न) परन्त्—
 - (i) वास्तविक तिथि से पूर्व भूमि क्रय की गई हो;
 - (ii) सरकार की संतुष्टि हो गई हो कि उद्योग की आवश्यकता इस प्रकार की है कि उपयुक्त अंचल में वैकल्पिक स्थल के आबंटन की प्रतीक्षा नहीं की जा सकती;
 - (iii) भू-स्वामी, नियमों के अधीन यथा अपेक्षित भवन निर्माण के लिए अनुमति प्राप्त करता है; तथा
 - (iv) भू—स्वामी, निदेशक द्वारा निर्धारित अनुपातिक प्रभारों जब कभी इस निमित्त निदेशक द्वारा मांग की जाये, का भुगतान निदेशक को करने का वचन देता है और अंतरिम अवधि में बिहःस्राव के निकास की संतोषजनक व्यवस्था करता है।

व्याख्या:— विनियम में शब्द "क्रय" से अभिप्राय है; पूर्ण स्वामित्व अधिकारों का अर्जन करना तथा क्रय इत्यादि के करार के रूप में, कोई कमतर अधिकार नहीं।

XVIII. सघनता:-

दोनों ओर से 20 प्रतिशत की विभिन्नता सहित प्रत्येक रिहायशी सेक्टर, ड्राईग में दर्शायी गई सेक्टर सघनता तथा इसके अतिरिक्त, नई एकीकृत अनुज्ञापन पॉलिसी, दीन दयाल जन आवास योजना पॉलिसी तथा अफोर्डऐबल ग्रुप हारुसिंग पॉलिसी में यथा विहित सघनता में विकसित किया जाएगा। 20 प्रतिशत ग्रुप हारुसिंग कम्पोनन्ट पॉलिसी रिहायशी सेक्टर में भी लागू होगी।

XIX. कृषि अंचल में आबादी देह के बाहर फार्म गृहों की व्यवस्था:-

केवल भू—स्वामी (स्वामियों) को वास्तविक उपयोग के लिए फार्म गृहों की अनुमित दी जाएगी बशर्तें कि किसी शहरी क्षेत्र में उसका अपना कोई आवास नहीं हो, चूंकि कृषि अंचल में फार्म गृहों को अनुमत करने के लिए वास्तविक उद्देश्य फार्म के छोटे भाग पर कृषकों की आवासीय आवश्यकताओं को पूरा करना है, तािक वह उस फार्म पर निवास करने के दौरान अपने कृषि उत्पाद की देख—रेख कर सकें। इसिलए आबादी देह के बाहर कृषि अंचल में निम्नलिखित शर्तों पर फार्म गृह अनुमत किया जा सकता है, यदि भूमि का क्षेत्र 2 एकड़ या इससे अधिक है:

***************************************	राता र मा हुट अंद्रात किया का सकता है, यर हो। या बाह दे राज्य में इतता आयक है				
	फार्म हाउस का आकार	आवासीय इकाई का मुख्य	मुख्य आवासीय इकाई का		
		भवन	अनुषंगी भवन		
(i) स्थल	न्यूनतम २ एकड़ तक परन्तु विकास	250 वर्ग गज के समकक्ष	फार्म की भूमि का एक		
आच्छादन	योजना अनुसार सड़क आरक्षण तथा	रिहायशी प्लाट के लिये यथा			
	प्रस्तावित सड़क की चौड़ाई के अधीन	लागू।	के क्वार्टरों के लिए 40		
	आने वाली भूमि/क्षेत्र भूमि उपयोग में		प्रतिशत से अधिक का		
	परिवर्तन की अनुमति हेतु मान्य नहीं		उपयोग नहीं किया जायेगा)		
	होगी। किन्तु कृषि अंचल में आने वाले				
	आवेदित 2 एकड़ क्षेत्र में से हरित				
	पट्टी / प्रतिबधित पट्टी के अधीन आने				
	वाले क्षेत्र को छोड़ते हुए शेष क्षेत्र 1.5				
	एकड़ से कम नहीं होना चाहिए।				

फार्म हाउस का आकार	आवासीय इकाई का मुख्य भवन	मुख्य आवासीय इकाई का अनुषंगी भवन
3 एकड़ तक	375 वर्ग गज के समकक्ष रिहायशी प्लाट के लिये यथा लागू।	—सम <u>—</u>
4 एकड़ तक और अधिक	500 वर्ग गज के समकक्ष रिहायशी प्लाट के लिये यथा लागू।	- सम-
(ii) ऊंचाई तथा मंजिल	11 मीटर, तीन मंजिलें	4 मीटर एक मंजिल

(iii) दूरीः

कृषि भूमि के सभी किनारों से कम से कम 10 मीटर दूर बशर्तें कि यदि फार्म हाऊस से संबद्ध भूमि सड़क के साथ लगती है तो गृह का निर्माण सड़क के किनारे से कम से कम निम्नलिखित दूरी पर किया जायेगा:—

क्रम संख्या	सडक	चौड़ाई
(ক)	जहां सड़क अनुसूचित सड़क का बाईपास है	100 मीटर
(ख)	जहां सड़क अनुसूचित सड़क है	30 मीटर या जैसा विकास योजना में दर्शाया गया है।
(ग)	कोई अन्य सड़क	10 मीटर

(iv) पहुँच सड़क:-

राजस्व रिकार्ड में परिभाषित कोई राजस्व रास्ता / सड़क।

(v) तहखाना:-

तहखाना, भू—तल आच्छादन की अधिकतम सीमा तक अनुमत किया जाएगा और उपयोग हरियाणा भवन संहिता, 2017 के अनुसार अनुज्ञात हैं।

(vi) पुश्तवान, अटारी तथा परछती तल:-

पुश्तवान, अटारी और परछती तल की अनुमित भवन के भीतर उक्त निर्बन्धनों के साथ—साथ विकास योजना के अंचल विनियमों के खण्ड—II में दी गई परिभाषा में नियत निर्बन्धनों के अध्यधीन दी जायेगी।

(vii) सेवायें, जल आपूर्ति तथा जल-निकास:-

- (क) यदि फार्म गृह का निर्माण किया जाता है, तो फार्म में मानव उपयोग के लिए अच्छी पीने योग्य जल आपूर्ति उपलब्ध होनी चाहिए।
- (ख) डेरी फार्म के मामले में छायावानों की सफाई हेतु खुली स्वच्छ निकास नालियां अथवा ढकी हुई निकास नालियों की व्यवस्था की जाये, सभी भवनों के मामले में, वर्षा जल के निकास हेतु निकास नालियों की व्यवस्था की जानी है।
- (ग) नियमों के उपबन्धों के अनुसार मानव और पशुओं के अपशिष्ट निस्तारण के लिए मलाश्य की व्यवस्था की जाये।
- (घ) मलाश्य और खुले कुएं अथवा नलकूप के बीच दूरी नियमों में यथा उपबन्धित अनुसार होगी ;
- (viii) स्वामी को फार्म हाऊस की मुख्य आवासीय इकाई और उसके अनुषंगी भाग के इर्द–गिर्द चार दीवारी के निर्माण की अनुमित दी जायेगी तथा फार्म के शेष क्षेत्र के इर्द–गिर्द कंटीली तारों वाली बाड लगाने की अनुमित होगी।
- (ix) केन्द्रीय भूजल बोर्ड द्वारा यथा घोषित अत्यधिक शोषित अथवा सकंटमय क्षेत्र से भिन्न क्षेत्र में फार्म हाऊस की स्थापना हेतु भूमि उपयोग में परिवर्तन की अनुमति पर विचार किया जायेगाः

परन्तु सरकार कृषि अंचल के उचित उपयोगिता के लिए राज्य सरकार/राज्य अभिकरण द्वारा प्रायोजित किसी स्कीम के लिए फार्म के न्यूनतम आकार में संशोधन कर सकती है।

XX. सूचना प्रौद्योगिकी इकाईयों और साईबर पार्कों / साईबर शहरों के लिए उपबन्ध:-

(i) अवस्थिति :-

- (क) सूचना प्रौद्योगिकी इकाईयां केवल औद्योगिक क्षेत्र/औद्योगिक अंचल में अवस्थित होंगी;
- (ख) साईबर पार्क / सूचना प्रौद्योगिकी पार्क एकीकृत विकास के रूप में सैक्टर सड़क के साथ लगते हुए या तो औद्योगिक क्षेत्र या औद्योगिक अंचल में अवस्थित होंगे। यद्यपि, ऐसे पार्कों में किन्हीं विनिर्माण इकाईयों को अनुज्ञात नहीं किया जाएगा।

(ग) - साईबर शहर :- ऐसी सुविधा की अवस्थिति सरकार द्वारा सुनिश्चित की जाएगी।

(ii) आकार :-

क्रम संख्या	प्रकार	आकार
1	सूचना प्रौद्योगिकी औद्योगिक इकाई	1 से 5 एकड़
2	साईबर पार्क / सूचना प्रौद्योगिकी पार्क	5 से 15 एकड़
3	साईबर सिटी	न्यूनतम ५० एकड़

(iii) विविध:-

(I) पार्किंग:-

पार्किंग, समय समय पर यथा संशोधित, हरियाणा भवन संहिता, 2017 के उपबन्धों के अनुसार होगी।

(II) अन्य क्रिया कलाप:-

- (क) आनुषांगिक वाणिज्यिक क्रियाकलाप जैसे बैंक, रैस्टोरैन्ट, इंश्योरैंस कार्यालय इत्यादि, को साईबर पार्क / सूचना प्रौद्योगिकी पार्क के कुल क्षेत्र के 4 प्रतिशत निर्बन्धन के अधीन रहते हुए अनुमति दी जायेगी:
- (ख) साईबर शहर के क्षेत्र का केवल 5 प्रतिशत क्षेत्र वर्ग आवास के लिए अनुमत किया जायेगा तथा इस साईबर शहर का कुल क्षेत्र 4 प्रतिशत वाणिज्यिक / संस्थागत उपयोगों के लिए अनुमत किया जायेगा:
- (ग) साईबर शहर में रिहायशी प्लाटिड विकास की अनुमति नहीं दी जायेगी;
- (घ) किसी साईबर शहर परियोजना के लिए यदि कृषि अंचल में अनुज्ञात हो, तो उद्यमी जल–आपूर्ति तथा अन्य सुविधाओं जैसे मल <u>जलनिस्तारण/निकास</u> नालियां इत्यादि का प्रबन्ध करेगा।
- (III) सरकार, कोई अन्य शर्त अधिरोपित कर सकती है, जैसा समय–समय पर आवश्यक समझे।

XXI. संचार टावरों की स्थापना:-

नियंत्रित क्षेत्र के भीतर संचार टावर स्थापित करने के लिए अनुमित, समय—समय पर यथा सशोंधित विभाग की पालिसी/अनुदेशों दिनांक 10 मार्च, 2015 के अनुसार प्रदान की जाऐगी।

XXII. भूकंम्पीय आपदा से सुरक्षा:-

भारतीय मानक आई. एस. 1893:2002 के भूकम्पीय क्षेत्र मानचित्र के अनुसार विकास योजना का क्षेत्र भूकम्पीय क्षेत्र जोन III अंतर्गत आता है तथा इसे उच्च जोखिम क्षेत्र माना गया है। उपरोक्त को ध्यान में रखते हुए, सम्पूर्ण शहरी विकास घटना तीव्रता 'VII' की सम्भाव्यता हेतु सुरक्षा की जांच की जाएगी तथा भवनों तथा अवसंरचना में अपेक्षित भूकम्पीय प्रतिरोध, जो आवश्यक पाया जाए, उन्नत किया जाएगा।

XXIII. नियंत्रित क्षेत्र में स्थित ईंटों के भट्टे:-

नियंत्रित क्षेत्रों में स्थित ईंट भट्टे सक्षम प्राधिकारी द्वारा समय-समय पर जारी सम्बंधित नीति/दिशा-निर्देशों के द्वारा शासित होंगें।

XXIV.विकास योजना में ढील:-

सरकार, अत्यन्त किठनाई की दशा में अथवा वास्तविक तिथि से पूर्व निर्मित किसी ढांचे को बचाने के दृष्टिगत ऐसे विकास प्रभारों के भुगतान पर और ऐसी अन्य शर्तों पर, जो वह लगाना उचित समझे, साम्य और न्याय के सिद्धान्तों पर विकास योजना के किसी भी उपबन्ध में ढील दे सकती है।

परिशिष्ट क भूमि उपयोगों का वर्गीकरण

मुख्य कोड	उपकोड	मुख्य वर्ग	उपवर्ग
100		रिहायशी	पड़ोस–पद्धति पर रिहायशी सैक्टर
200		वाणिज्यिक	
	210		परचून व्यवसाय
	220		थोक व्यवसाय
	230		भांडागार और भंडारण
	240		कार्यालय और बैंक जिसमें सरकारी कार्यालय भी शामिल हैं।
	250		रैस्तरां, होटल तथा अस्थाई बोर्डिंग हाऊस, जिनमें धर्मशाला, पर्यटक गृह आदि जैसे रिहायशी आवास की व्यवस्था वाली सार्वजनिक सहायता संस्थायें भी शामिल हैं
	260		वाणिज्यिक आधार पर सिनेमा तथा लोगों के एकत्रित होने वाले अन्य स्थान
	270		व्यवसायिक स्थापनायें
300		औद्योगिक	
	310		सेवा उद्योग
	320		हल्के उद्योग
	330		व्यापक उद्योग
400		परिवहन तथा	
		संचार	
	410		रेलवे यार्ड, रेलवे स्टेशन तथा साईडिंग
	420		सड़कें, सड़क परिवहन डिपो और पार्किंग क्षेत्र,
	450		टेलीग्राफ केन्द्र, दूरभाष केन्द्र इत्यादि
500		जन उपयोगितायें	
	510		जल आपूर्ति संस्थापन जिसमें शोधन संयंत्र भी शामिल हैं
	520		जल निकास और सफाई संस्थापनायें जिनमें निस्तारण कार्य भी शामिल हैं,
	530		विद्युत शक्ति संयंत्र उपस्टेशन इत्यादि
	540		गैस संस्थापन और गैस कार्य
	550		टोस अपशिष्ट प्रबन्धन स्थल
600		सरकारी और अर्धसरकारी	
	610		सरकारी प्रशासन, केन्द्रीय सचिवालय, जिला कार्यालय, विधि न्यायालय, जेलें, पुलिस थाने, राज्यपाल तथा राष्ट्रपति निवास
	620		शिक्षा, सांस्कृतिक और धार्मिक संस्थायें
	630		चिकित्सा तथा स्वास्थ्य संस्थायें
	640		मुख्यतः गैर वाणिज्यिक किस्म के थियेटर, आपेरा हाऊस इत्यादि जैसी सांस्कृतिक संस्थायें
700 खुले स्थान			
	710		खेलकूद मैदान, स्टेडियम, क्रीड़ा मैदान
	720		पार्क

मुख्य कोड	उपकोड	मुख्य वर्ग	उपवर्ग			
	730		हरित पट्टी, बाग, कृषि वानकी / फूलों की खेती तथा अन्य मनोरंजन संबंधी उपयोग			
	740		कब्रिस्तान, शमशान घाटइत्यादि			
	750		ईंधन स्टेशन तथा बस पंक्ति शैल्टर			
	760		जल निकाय / झीलें			
800		कृषि भूमि				
	830		प्रधान फसल के अधीन भूमि			
	850		वन भूमि			
	880		जलमग्न भूमि			
	890		डेरी फार्मिंग			
900		विशेष अंचल	आमोद—प्रमोद, मनोरंजन तथा वाणिज्यिक गतिविधियों (मिश्रित भूमि उपयोग)			

परिशिष्ट-ख

मुख्य भूमि उपयोगों के अधीन दी गई अनुमत गतिविधियां, सरकार द्वारा स्वीकृत पालिसी/मापदंडों तथा सेक्टर/कालोनी में सक्षम प्राधिकारी द्वारा स्थल पर यथा अनुमत अनुसार अनुमत की जाएगी।

I. रिहायशी अंचल

- (i) आवासीय।
- (ii) सामाजिक, सामुदायिक, धार्मिक और आमोद-प्रमोद गृह।
- (iii) जन उपयोगिता भवन।
- (iv) शैक्षणिक भवन और सभी प्रकार के विद्यालय और महाविद्यालय, जहाँ आवश्यक हों।
- (v) स्वास्थ्य संस्थायें।
- (vi) सिनेमा।
- (vii) वाणिज्यिक और व्यवसायिक कार्यालय।
- (viii) परचून की दुकानें, ढाबे और रैस्तरां।
- (ix) स्थानीय सेवा उद्योग।
- (x) ईंधन स्टेशन।
- (xi) बस स्टाप, तांगा, टैक्सी, स्कूटर तथा ऑटो/रिक्शा स्टैंड।
- (xii) नर्सरियां और हरित गृह।
- (xiii) रिहायशी उपयोग में अनुषंगी कोई अन्य छोटी–छोटी जरूरतें।
- (xiv) सितारा होटल।
- (xv) क्लब/सामुदायिक केन्द्र।
- (xvi) संचार टावर।
- (xvii) अतिथि / बोर्डिंग आवास।
- (xviii) कोई अन्य उपयोग, जिसे सरकार लोकहित में विनिश्चित करे।

II. वाणिज्यिक अंचल

- (i) परचून व्यापार।
- (ii) थोक व्यापार।
- (iii) भांडागार और भंडारण।
- (iv) वाणिज्यिक कार्यालय और बैंक।
- (v) रैस्तरां तथा अस्थाई आवास गृह जिसमें धर्मशाला और पर्यटक गृह आदि जैसे रिहायशी स्थान प्रदान करने वाले सार्वजनिक सहायता संस्थाएं शामिल हैं।

- (vi) सिनेमा, होटल, मोटल तथा वाणिज्यिक आधार पर चलने वाले और लोगों के इकट्ठा होने वाले अन्य स्थान जैसे थियेटर, क्लब, ड्रामा क्लब आदि।
- (vii) व्यावसायिक स्थापनायें।
- (viii) प्रथम तथा उच्चतर मंजिलों पर निवास।
- (ix) स्थानीय सेवा उद्योग।
- (x) जन उपयोगिता भवन।
- (xi) ईंधन स्टेशन और सर्विस गैरेज।
- (xii) माल चढ़ाने और उतारने वाले यार्ड।
- (xiii) पार्किंग स्थल, बस स्टाप, टैक्सी, तांगा, आटो/रिक्शा स्टैंड।
- (xiv) नगर पार्क।
- (xv) संचार टावर।
- (xvi) कोई अन्य उपयोग, जिसे सरकार लोकहित में विनिश्चित करे।

III औद्योगिक अंचल

- (i) हल्के उद्योग।
- (ii) मध्यम उद्योग।
- (iii) घृणाजनक और परिसंकटमय उद्योग।
- (iv) भारी उद्योग।
- (v) सर्विस उद्योग।
- (vi) भांडागार और भंडारण।
- (vii) पार्किंग, माल चढाने और उतारने वाले क्षेत्र।
- (viii) ट्रक स्टैंड / बस स्टाप, टैक्सी तांगा और आटो / रिक्शा स्टैंड।
- (ix) सेक्टर के कुल क्षेत्र की अधिकतम तीन प्रतिशत की सीमा के अध्यधीन जन उपयोगिता, सामुदायिक भवन, परचून की दुकानें, बैंक, ढाबे, रैस्टोरैन्ट, दो/ तीन /पांच सितारा होटल तथा बीमा कार्यालयनिम्नानुसार हैं:—

क्रम	सुविधा	क्षेत्र		सैक्टर में	वाणिज्यिक	अधिकतम	फर्श क्षेत्र	पहुँच सड़क
संख्या	का नाम	न्यूनतम	अधिकतम	कुल सुविधाएं	घटक	भूतल आच्छादन	अनुपात	
1	ढाबा	500 वर्गमीटर	1000 वर्गमीटर	2	50 वर्गमीटर	40 प्रतिशत	0.40	न्यूनतम 18 मीटर
2	रैस्टोरैन्ट	1000 वर्गमीटर	2000 वर्गमीटर	2	10 प्रतिशत	30 प्रतिशत	1.50	न्यूनतम 18 मीटर
3.	दो / तीन सितारा होटल	1.0 एकड	2.5 एकड	2	15 प्रतिशत	30 प्रतिशत	वाणिज्यिक नीतिनुसार	न्यूनतम 24 मीटर
4.	पांच सितारा होटल	2.5 एकड	4 एकड़	1	15 प्रतिशत	30 प्रतिशत	वाणिज्यिक नीतिनुसार	सेक्टर विभाजित सडक जिस पर सर्विस सडक का प्रावधान हो।

- (x) ईंधन स्टेशन तथा सर्विस गैरेज।
- (xi) निदेशक द्वारा अनुमत लिक्वीड पैट्रोलियम गैस गोदाम।
- (xii) साईबर पार्क / सूचना प्रौद्योगिकी पार्क / सूचना प्रौद्योगिकी औद्योगिक इकाइयां।
- (xiii) स्वास्थ्य सुविधाएं जैसे अस्पताल, औषधालय, नर्सिंग होम तथा क्लीनिकः

क्रम	सुविधा का	क्षेत्र		सैक्टर	रिहायशी	अधिकतम	দূর্ঘ
संख्या	नाम	न्यूनतम	अधिकतम	में कुल सुविधाएं	घटक	भूतल आच्छादन	क्षेत्र अनुपात
				3			-
1	अस्पताल	2.5 एकड	5 एकड़	1	15 प्रतिशत	३३ प्रतिशत	1.00
2	औषधालय	1.0 एकड	1.5 एकड	1	15 प्रतिशत	33 प्रतिशत	1.00
3	नर्सिंग होम	250वर्गमीटर	500वर्गमीटर	2	शून्य	60 प्रतिशत	1.00

4. क्लीनिक 250	वर्गमीटर 500वर्गमीटर	2	शून्य	60 प्रतिशत	1.00]
----------------	----------------------	---	-------	------------	------	---

- (xiv) आँद्योगिक कालोनी कम से कम 15 एकड़ में होगी। इस क्षेत्र का उपयोग अपर मुख्य सचिव, नगर तथा ग्राम आयोजना विभाग हरियाणा की यथा अद्यतन संशोधित पालिसी संख्या मिसलेनियस 388/पी.ए. (आरबी)/2015/7/16/2006—2टीसीपी, दिनांक प्रथम अक्तूबर, 2015 के अनुसार होगा।
- (xv) संचार टावर।
- (xvi) तैयार मिश्रण कंकीट संयत्र, वेट मिश्रण संयत्र, गर्म मिश्रण संयत्र इत्यादि।
- (xvii) धर्म कांटा।
- (xviii) सर्विस गैरज, बिक्री / प्रदर्शन केन्द्र-एवं-सर्विस गैरज का विवरण निम्न अनुसार है:-

क्रम	सुविधा	क्षेत्र (१	रकड़ में)	वाणिज्यिक	अधिकतम	দূর্ঘ	पहुंच मार्ग	ऊँचाई
संख्या	का नाम	न्यूनतम	अधिकतम	घटक	भूतल	क्षेत्र		
					आच्छादन	अनुपात		
1	सर्विस गैरज	0.5	1	शून्य	60 प्रतिशत	1.25	न्यूनतम 18 मीटर या सेक्टर सड़क के साथ प्रस्तावित सर्विस सड़क	18 ਸੀਟਾ
2	बिक्री / प्रदर्शन केन्द्र-एवं- सर्विस गैरज	0.5	2	अनुज्ञेय फर्श क्षेत्र अनुपात का १० प्रतिशत	60 प्रतिशत	1.25	न्यूनतम 18 मीटर या सेक्टर सड़क के साथ प्रस्तावित सर्विस सड़क	18 मीटर

टिप्पण:-*वाणिज्यिक घटक के विषय में फीस तथा प्रभार वाणिज्यिक दरों पर उदगृहीत किए जाएंगे;

- * विद्यमान/पहले से भूमि उपयोग परिवर्तन अनुमित प्राप्त सर्विस गैराज को बिकी/प्रदर्शन केन्द्र की अनुमित देने हेतु उपरोक्त मानदण्डों को पुरा करने के अध्यधीन विचारा जाएगा।
- (xix) कोई अन्य उपयोग, जिसे सरकार लोकहित में विनिश्चित करे।

IV परिवहन तथा संचार अंचल

- (i) रेलवे यार्ड, रेलवे स्टेशन और साईडिंग।
- (ii) परिवहन नगर, सडकें और परिवहन डिपो और पार्किंग क्षेत्र।
- (iii) हवाई अड्डा और हवाई स्टेशन।
- (iv) दूरभाष केन्द्र।
- (v) प्रसारण केन्द्र।
- (vi) दूरदर्शन केन्द्र।
- (vii) अनुमोदित स्थलों और स्थानों पर कृषि, बागवानी और नर्सरिज।
- (viii) ईंधन स्टेशन और सर्विस गैरेज।
- (ix) पार्किंग स्थल, बस स्टाप-शैल्टर, टैक्सी, टांगा और ओटो / रिक्शा स्टैंड।
- (x) रसद केन्द्रों / कंटेनर यार्डस, अंर्तदेशीय कंटेनर डिपो, कंटेनर फेट स्टेशन।
- (xi) धर्म कांटा।
- (xii) संचार टावर।
- (xiii) सेक्टर के कुल क्षेत्र की अधिकतम 20 प्रतिशत की सीमा तक भांडागार।
- (xiv) वर्तमान नीति के अनुसार ढाबा।

V जनउपयोगितायें

- (i) जल सप्लाई, संस्थापनाएं जिसमें शोधन संयंत्र भी शामिल हैं।
- (ii) जल निकास और सफाई स्थापनाएं इसमें मलजल शोधन संयंत्र तथा निपटान कार्य भी शामिल हैं।
- (iii) विद्युत शक्ति संयंत्र तथा सबस्टेशन जिसमें ग्रिड सब-स्टेशन भी शामिल हैं।
- (iv) गैस संस्थापनाएं तथा गैस वर्कस।
- (v) टोस अपशिष्ट प्रबन्धन स्थल।

VI सार्वजनिक तथा अर्धसार्वजनिक उपयोग अंचल

(i) सरकारी कार्यालय, सरकारी प्रशासन केन्द्र, सचिवालय और पुलिस थाना।

- (ii) शैक्षणिक, सांस्कृतिक और धार्मिक संस्थायें।
- (iii) चिकित्सा स्वास्थ्य संस्थायें।
- (iv) नागरिक / सांस्कृतिक और सामाजिक संस्थान जैसे थियेटर, ओपेरा हाउस इत्यादि जो मुख्यतः गैर वाणिज्यिक किस्म के हों।
- (v) रक्षा से सम्बन्धित भूमि।
- (vi) ढाबा, रेस्टोरेन्ट निम्न अनुसार:-

क्रम संख्या	सुविधा	8	क्षेत्र		वाणिज्यिक	अधिकतम	फर्श क्षेत्र
	का नाम	न्यूनतम	अधिकतम	कुल सुविधाओं की संख्या	घटक	भूतल आच्छादन	अनुपात
ढाबा	500 वर्गमीटर	1000 वर्गमीटर	2	50 वर्गमीटर	50 प्रतिशत	50 प्रतिशत	
रैस्टोरैन्ट	1000 वर्गमी0	2000 वर्गमी0	2	10 प्रतिशत	30 प्रतिशत	150 प्रतिशत	

- (vii) संचार टावर।
- (viii) ईंधन स्टेशन।
- (ix) कोई अन्य उपयोग, जिसे सरकार लोकहित में विनिश्चित करे।

VII खुले स्थान

- (i) खेलकूद मैदान, स्टेडियम तथा कीड़ा मैदान।
- (ii) पार्क तथा हरित पट्टी, बाग तथा अन्य मनोरंजनात्मक उपयोग।
- (iii) कब्रिस्तान, शमशान घाट इत्यादि।
- (iv) निदेशक की अनुमित से सड़कों के साथ ईंधन स्टेशन, बस पंक्ति/शैल्टर।
- (v) अनुसूचित सड़कों तथा मुख्य सड़कों के साथ हरित पट्टी में सार्वजनिक उपयोगिता सेवाएं जैसे इलैक्ट्रक ग्रिड स्टेशन, प्रेषण लाईनें, संचार लाईनें, जल आपूर्ति लाइनें सीवरेज लाईनें, ड्रैनेज लाईनें।
- (vi) जल निकाय/झील/जल पूर्नभरण क्षेत्र।
- (vii) संचार टावर।
- (viii) मेला स्थल तथा बह् उपयोगी मैदान।
- (ix) कोई अन्य उपयोग, जिसे सरकार लोकहित में विनिश्चित करे।

VIII कृषि अंचल

- (i) कृषि, बागवानी, डेरी और मुर्गी पालन।
- (ii) आबादी देह के भीतर गांव घर।
- (iii) अंचल विनियम XIX में यथा निर्धारित निर्बन्धनों के अध्यधीन, आबादी देह के बाहर फार्म हाऊस।
- (iv) वन रोपण विकास तथा मनोरंजन के लिए उसका कोई भाग।
- (v) आबादी देह के समीप वर्तमान गांव का विस्तार यदि यह परियोजना, केन्द्र सरकार या राज्य सरकार द्वारा अनुमोदित या प्रायोजित हो।
- (vi) दुग्ध अवशीतन केन्द्र और पैस्चयूरीकरण केन्द्र।
- (vii) बस अड्डा और रेलवे स्टेशन।
- (viii) अनिवार्य भवनों सहित हवाई अड्डा।
- (ix) बेतार केन्द्र।
- (x) निदेशक द्वारा अनुमोदित स्थलों पर अनाज गोदाम, भंडारण स्थल।
- (xi) मौसम कार्यालय ।
- (xii) भू-जल निकास और सिंचाई, पन बिजली कार्य और सिंचाई के लिए नलकूप।
- (xiii) टेलीफोन और बिजली प्रेषण लाईनें ओर खम्भे।
- xiv) खनन तथा उत्खनन कार्य जिसमें चूना तथा ईंटों के भट्टे, पत्थर, खदानें और क्रेशिंग शामिल है, जो नियमों तथा अनुमोदित स्थल पर, के अधीन रहते हुए हैं।
- (xv) शमशान और कब्रिस्तान।

- (xvi) ईंधन स्टेशन और सर्विस गैरेज।
- (xvii) नवीकरणीय और गैर नवीकरणीय उर्जा शक्ति संयंत्र।
- (xviii निदेशक के अनुमोदन से तरल पैट्रोलियम पदार्थ भण्डारण गोदाम।
-) लघु उद्योग औद्योगिक इकाइयों को निम्नलिखित शर्तों की पूर्ति के अधीन रहते हुए अनुमित दी जाएगी, (xix) बशर्तें ऐसा स्थल रक्षा संस्थापनाओं, यदि कोई हो, के इर्द गिर्द रक्षा संकर्म अधिनियम, 1903 (1903 का केन्द्रीय अधिनियम 7) के अधीन वर्जित पट्टी के भीतर नहीं होना चाहिए।

क. स्थल मानदंड		
अंचल	मानदंड	
कम संभावित क्षेत्र	शहरीकरण क्षेत्र से 2 किमी के भीतर (परिधीय सड़कों को छोड़कर, यदि शहरी सीमा पर प्रस्तावित किया गया हो)	शहरीकरण क्षेत्र से 2 किमी से अधिक (परिधीय सड़कों को छोड़कर, यदि शहरी सीमा पर प्रस्तावित किया गया हो)
	किसी भी क्षेत्र की गैर—प्रदूषणकारी हरी किसी भी क्षेत्र की ग्री श्रेणी इकाइयां नारंगी श्रेणी इकाइयां	
ख. पहुँच मानदंड		
निम्न संभावित न्यून क्षेत्र जाप चौड उप आवे कि	योगिक उपयोग के लिए कृषि क्षेत्र में भूमि उप ततम 30 फीट चौड़ा राजस्व सड़क / सा एगा । तथापि, यदि भूमि उपयोग की औद्यो। हा राजस्व मार्ग / सार्वजनिक सड़क पर दी योग परिवर्तन अनुमति के लिए आवेदन, इस श् वेदन करने वाले साइट के सामने 6 कर्म (33 प 1 करम (5.5 फुट) चौड़ी पट्टी ग्राम पंच बानैमा / उपहार के माध्यम से विस्तृत पट्व गई भूमि ।	र्वजनिक सड़क पर विचार किया गिक परिवर्तन 5 करम (27.5 फुट) गई है, तो उस सड़क पर भूमि गर्त के अध्यधीन विचारा जाएगा कि मुट) परियोजना प्रत्यार्तक दर्शाता है ग्रायत / स्थानीय प्राधिकरण को

- (xx) अनुसूचित सड़कों, राष्ट्रीय राजमार्ग और राज्य राजमार्ग के अलावा सार्वजनिक सड़क / रास्ता जिसकी चौड़ाई 30 फीट से कम है, पर गैर प्रदूषणकारी मध्यम और बड़े पैमाने पर कृषि आधारित उद्योग;बशर्ते कि ऐसी स्थापना, यदि कोई हो, के लिए यथा लागू सुरक्षा स्थापना के आसपास निर्बन्धित पट्टी के भीतर नहीं होना चाहिए ।
- (xxi) निर्बन्धित / हरित पट्टी के बाहर क्षेत्र में राष्ट्रीय राजमार्ग / अनुसूचित सड़कों के साथ ढाबे, बैंक्विट हाल, लघु रैस्टोरैन्ट, मोटल, होटल रिर्सोटज तथा मन बहलाव पार्क / थीम पार्क निम्न अनुसार होंगेः

क्रम	अनुज्ञेय	8	क्षेत्र	वाणिज्यक	अधिकतम	फर्श क्षेत्र
संख्या	गतिविधि	न्यूनतम	अधिकतम	घटक	भूतल आच्छादन	अनुपात
1	ढाबा	1000 वर्ग	1.0 एकड़	<u>50 वर्ग मीटर</u>	40 प्रतिशत	40
		मीटर				प्रतिशत
2	रैस्टोरैन्ट	2000 वर्ग मीटर	1.0 एकड़	<u> 15 प्रतिशत</u>	30 प्रतिशत	150 प्रतिशत
3	बैंकट सुविधाओं सहित मोटल	2.5 एकड़	5 एकड़	<u> 15 प्रतिशत</u>	30 प्रतिशत	150 प्रतिशत
4	रिर्सोट	4.0 एकड़	10 एकड़	15 प्रतिशत	30 प्रतिशत	150 प्रतिशत
5	मन–बहलाव पार्क / थीम पार्क	2.5 एकड़	10 एकड़	15 प्रतिशत	30 प्रतिशत	50 प्रतिशत

परन्तु पहुंच अनुज्ञा, यदि स्थल राष्ट्रीय राजमार्ग पर अवस्थित है, तो भारतीय राष्ट्रीय राजमार्ग प्राधिकरण तथा यदि स्थल अनुसूचित सड़क पर अवस्थित है, तो कार्यकारी अभियन्ता, लोक निर्माण विभाग (भवन तथा सड़कें) से प्राप्त की गई है।

(xxii) बेंक्विट हाल:-

अनुज्ञेय अचंल	कृषि अचंल
पहुंच	1. पहुंच सड़क की न्यूनतम चौडाई 18 मीटर होनी चाहिए।
	2. यदि स्थल अनुसूचित सड़क पर स्थित हो, तो पहुंच अनुज्ञा कार्यकारी
	अभिंयता, लोक निर्माण विभाग (भवन तथा सड़कें) से अपेक्षित है।
	3. राष्ट्रीय राजमार्ग से भी पहुंच विचारी जा सकती है, यदि स्थल
	चौराहा / पहुंच मार्ग से न्यूनतम दूरी मानक पूरा क्रता हो तथा न्यूनतम
	7 मीटर चौड़ी सेवा सड़क पर अवस्थित हो यो आवेदक भारतीय राष्ट्रीय
	राजमार्ग प्राधिकरण से पहुंच की पूर्व अनुज्ञा प्रस्तुत करता है।
अपेक्षित क्षेत्र	न्यूनतम २.५ एकड्
	अधिकतम ५.०० एकड्
फर्श क्षेत्र अनुपात	50 प्रतिशत
भूतल आच्छादन	30 प्रतिशत
परिवर्तन प्रभार	वाणिज्यिक उपयोग के लिए विहित दर का 50 प्रतिशत
फर्श क्षेत्र अनुपात के	उपहार दुकान, एस टी डी बूथ, खिलौना केन्द्र तथा फूलों की दूकानें इत्यादि
भीतर अनुज्ञेय	के लिए अनुमत फर्श क्षेत्र अनुपात का 10 प्रतिशत
अनुषांगिक उपयोग	
पार्किंग	स्थल क्षेत्र का न्यूनतम 25 प्रतिशत

टिप्पण:-

नगरपालिका सीमा के भीतर विवाह महल/बाँक्विट हाँल की व्यवस्था शहरी स्थानीय निकायों के विभाग द्वारा अनुमोदित तथा समय समय पर संशोधित नीति के अनुसार होगा ।

- (xxiii) माईक्रोवेव टावर/स्टेशन, भूकम्प केन्द्र तथा दूरसंचार केन्द्र।
- (xxiv) संचार टावर।
- (xxv) सरकार या सरकारी एजेंसी द्वारा संविदा अथवा कार्य हेतु अल्पाविध के लिए लगाए जाने वाले तैयार मिश्रण कंकीट संयंत्र, वेट मिश्रण संयंत्र, गर्म मिश्रण संयंत्र इत्यादि।
- (xxvi) सर्विस गैरज, बिक्री / प्रदर्शन केन्द्र-एवं-सर्विस गैरज का विवरण निम्न अनुसार है:-

क्रम	सुविधा का	क्षेत्र (प	रकड़ में)	वाणिज्यिक	अधिकतम	फर्श	पहुंच मार्ग	उंचाई
संख्य	नाम	न्यूनतम	अधिकतम	घटक	भूतल	क्षेत्र	मार्ग	
Т					आच्छादन	अनुपात		
1	सर्विस गैरज	0.5	1	शून्य	60 प्रतिशत	1.25	18 मीटर या सेक्टर सड़क के साथ सर्विस सड़क	18 मीटर
2	बिकी / प्रदर्शन केन्द्र— एवं—सर्विस गैरज	0.5	2	अनुज्ञेय फर्श क्षेत्र अनुपात का 10 प्रतिशत	60 प्रतिशत	1.25	18 मीटर या संक्टर सड़क के साथ सर्विस सड़क	18 मीटर

टिप्पणः *वाणिज्यिक घटक के विषय में फीस तथा प्रभार वाणिज्यिक दरों पर उद्गृहीत किए जाएंगे;

*विद्यमान / पहले से भूमि उपयोग परिवर्तन अनुमित प्राप्त सर्विस गैराज को बिकी / प्रदर्शन केन्द्र
की अनुमित देने हेत उपरोक्त मानदण्डों को परा करने के अध्यधीन विचारा जाएगा।

(xxvii) धर्म काटा।

(xxviii) कोई अन्य उपयोग, जिसे सरकार लोकहित में विनिश्चित करे।

IX विशेष अंचल:-

आमोद-प्रमोद, मनोरंजन तथा वाणिज्यिक गतिविधियों (मिश्रित भूमि उपयोग)।

X बिल्कुल निषिद्ध उपयोग:-

उचित अनुज्ञप्ति के बिना पैट्रोलियम और अन्य प्रज्जवलनीय सामग्री का भंडारण

परिशिष्ट-1

सूचना प्रौद्योगिकी उद्योग के स्कोप/परिभाषा में सिम्मिलित किए गए उद्योगों की श्रेणियां :--

(क) कम्प्यूटर डिवाईसिज के अन्तर्गत :--

डैस्क्टाप

पर्सनल कम्पयुटरस

सरवर्स

वर्क स्टेशन

नोडस

टरमिनलस

नैटवर्क पी.सी.

होम पी.सी.

लैपटॉप कम्पयटरस

नोट बुक कम्पयूटरस

पामटॉप कम्पयूटरर्स / पी.डी.ए.

(ख) नैटवर्क कंट्रोलर कॉर्ड / मेमोरी के अन्तर्गत :--

नैटवर्क इन्टरफेस कार्ड (एन.आई.सी.)

एडोप्टर इथरनेट / पी.सी.आई. / ई.आई.एस.ए. / कोम्बो / पी.सी.एम.आई.सी.ए.

एस.आई.एम.एम.मेमारी

डी.आई.एम.एम.मेमोरी

सैन्ट्रल प्रोसैंसिग यूनिट(सी.पी.यू.)

कन्ट्रोलर एस.सी.एस.आई. / ऐरे

प्रोसैसर का प्रौसेसर / प्रोसैसर पावर मोडयूल / अपग्रेड

(ग) स्टोरेज यूनिटस के अन्तर्गत :-

हार्ड डिसक ड्राईवस/हार्ड ड्राईवस

आर.ए.आई.डी. डिवाईसिस एवं उसके कन्ट्रोलर

फलोपी डिस्क डाईव

सी.डी.रोम डाईव

टेप ड्राईवस डी.एल.टी. ड्राईवस/डी.ए.टी.

आपटिकल डिस्क ड्राईव

अन्य डिजीटल स्टोरेज डिवाईज

(घ) अन्य :--

की बोर्ड

मोनीटर

माऊस

मल्टीमीडिया किट्स

(ड.) प्रिन्टर तथा आऊटपुट डिवाईसिस के अन्तर्गत :--

डोट मैट्रिक्स

लेजरजेट

इन्कजैट डेस्कजैट

एल.ई.डी. प्रिन्टर्स

लाईन प्रिन्टर्स

प्लाटर्स

पास बुक प्रिन्टर्स

(च) नेटवर्किंग उत्पाद के अन्तर्गत:-

हब्ज

रूटर्स

स्विचिस

कोन्सनटेटर्स

ट्रांसरिसिवर्स

(छ) सोफटवेयर के अन्तर्गत :--

एप्लीकेशन्स साफटवेयर आपरेटिंग सिस्टम

मिडल वेयर/फर्म वेयर

(ज) कम्पयूटर सिस्टम के लिए लगने वाली पावर सप्लाई के अन्तर्गत :--

स्विच मोड पावर सप्लाई अनइन्टरप्टिड पावर सप्लाई

(झ) नेटवर्किंग / केबलिंग तथा उससे संबंधित उपकरण :--

(सूचना प्रौद्योगिकी उद्योग से संबंधित)

फाईबर केबल

कोपर केबल

केबल्स

कनैक्टर्स, टरिमनल ब्लाक

जैक पैनल्स, पैच कोर्ड

माऊटिंग कोर्ड / वायरिंग ब्लाक

सरफेस माउंट बक्से

(ञ) कन्ज्यूमेबल्स के अन्तर्गत :--

सी.डी.रोम / कम्पैक्ट डिस्क

फलोपी डिस्क

टैप्स डी.ए.टी. / डी.एल.टी.

रिबन्स

टोनर्स

इन्कजैट कारटेजिस

आऊटपुट डिवाईसिस को लगने वाली इंक

(ट) इलैक्ट्रोनिक कम्पोनेन्ट :--

प्रिंटिड सर्किट बोर्ड/पापुलेटिड पी.सी.बी.

प्रिंटिड सर्किट बोर्ड / पी.सी.बी.

ट्रांजिस्टर्स

इन्टैग्रेटिड सर्किट्स/आई.सी.

डायोड्स/थाईरिस्टर/एल.ई.डी.

रेसिस्टर्स

केपेसिटर्स

स्विचिस (ऑन/ऑफ, पुश बटन, रोकर्स इत्यादि)

प्लगस / सोकेट्स / रिलेज

मेगनेटिक हेड्स, प्रिन्ट हैड्स

कनेक्टर

माईक्रोफोन्स / स्पीकर्स

फयुजिस

(ठ) टैलीकम्यूनिकेशन इक्वीपमेन्ट के अन्तर्गत :--

टैलीफोन

विडियो फोन

फेसी माईल मशीन / फैक्स कार्ड

टैली प्रिन्टर्स / टैलेक्स मशीन

पी.ए.बी.एक्स. / ई.पी.ए.बी.एक्स. / आर.ए.एक्स. / एम.ए.एक्स. टैलीफोन एक्सचैंज

मल्टीप्लेक्सर्स / म्यूजिस

मोडम्स

टैलीफोन आन्सरिंग मशीन

टैलीकम्युनिकेशन्स स्वीचिंग एपरेटर्स

एन्टेना तथा मास्ट

वायरलैस डेटाकोम इक्वीपमेन्ट

रिसीविंग इक्वीपमेन्ट लाईक पेजर्स, मोबाईल / सैल्यूलर फोन इत्यादि

वी.एस.ए.टीज.

वीडियो कोनफोरेंसिंग इक्वीपमेन्ट'

वीडियो एवं डिजिटल सिंगनलिंग के लिए लगने वाले सैट टाप बक्से के अन्तर्गत

(ढ) सूचना प्रौद्योगिकी को समर्थ बनाने वाली सेवायें वह व्यवसायिक किया तथा सेवायें है जिसके अन्तिम उत्पाद / सेवायें जिनको :--

- भारत से बाहर वितरित करने के लिए
- संचार-जाल के लिए वितरित करने के लिए; तथा
- या तो बाहरी ठेके (बाहरी स्त्रोत) या उस कम्पनी के सुदूर गौण द्वारा उपलब्ध किया हुआ (बाहर अवस्थित

टिप्पण :-

सेवाएं जो इनमें शामिल नहीं हैं, :

- सुदूर उत्पादन / विनिर्माण ईकाईयां
- कम्पनियों के निगमित कार्यालय अथवा उनकी स्थानीय शाखाएं
- इन्टरनैट पर वास्तविक व्यवसाय

निम्नलिखित सेवाएं जो उपरोक्त दिये गये मानदण्ड पूर्ण करती हैं, सिम्मिलित होंगी :

- (i) बैंक ऑफिस आप्रेशन्स
- (ii) काल सैन्टरज
- (iii) कोन्टैन्ट डिवैल्पमैन्ट अथवा एनीमेशन
- (iv) डाटा प्रोसैसिंग
- (v) अभियान्त्रिकी तथा रचना
- (vi) ज्योग्राफिक इन्फोरमेशन सिस्टम सर्विसिज
- (viii) मानव संसाधन सेवायें
- (ix) बीमा दावा प्रोसेसिंग
- (x) लीगल डाटा बेस
- (xi) मैडीकल ट्रान्सक्रिप्शन
- (xii) पे-रोल
- (xiii) सुदूर रख-रखाव
- (xiv) राजस्व लेखाकरण
- (xv) वैब-साईट सर्विसेज

एस.एन.रॉय, अपर मुख्य सचिव, हरियाणा सरकार, शहरी स्थानीय निकाय विभाग। अपूर्व कुमार सिंह, प्रधान सचिव, हरियाणा सरकार, नगर तथा ग्राम आयोजना विभाग।

HARYANA GOVERNMENT

TOWN AND COUNTRY PLANNING DEPARTMENT

AND

URBAN LOCAL BODIES DEPARTMENT

Notification

The 3rd June, 2020

No. CCP (NCR)/FDP/SBD/2020/494.— In exercise of the powers conferred by sub-section (7) of section 203C of the Haryana Municipal Act, 1973 (24 of 1973), and sub-section (7) of section 5 of the Punjab Scheduled Roads and Controlled Areas Restriction of Unregulated Development Act, 1963 (Punjab Act 41 of 1963), with reference to Haryana Government, Urban Local Bodies Department and Town and Country Planning Department, notification No.CCP(NCR)/153/2019/1848, dated the 13th September, 2019, the Governor of Haryana hereby publishes the following Final Development Plan 2031AD Shahabad for Shahabad Controlled Area, Additional Controlled Area Shahabad, Controlled Areas pocket-I & pocket-II along National Highway number 44 (earlier named National Highway No.-1) alongwith restrictions and conditions, given in Annexure A and B applicable to the controlled areas specified in Annexure B.

Drawings

- Existing Land Use Plan Drawing No. DTP (KKR) 741/2000, dated the 26thMay, 2000, already published *vide* Haryana Government, Town and Country Planning Department notification No. CCP(NCR)/DDP/(SBD)/2008 /769, dated the 14th March, 2008.
- Existing Land Use Plan Drawing No. DTP (KK) 964/2010, dated 11.08.2010 (already published *vide* Haryana Government, Urban Local Bodies Department and Town and Country Planning Department notification No. CCP(NCR)/153/2019/1848, dated the 13th September, 2019).
- Existing Land Use Plan Drawing No. DTP (KK) 965/2010, dated 20.08.2010 (already published *vide* Haryana Government, Urban Local Bodies Department and Town and Country Planning Department notification No. CCP(NCR)/153/2019/1848, dated the 13th September, 2019).
- 4 Final Development Plan Drawing No. DTP (KK) 1160/2019, dated 12.10.2019.

Annexure-A

Explanatory Note on the Final Development Plan-2031 AD Shahabad.

I. Introduction:-

Shahabad was founded by the followers of Shahabudin Gauri in 1192 A.D. after the battle of Taraori. It is a Sub-division Markanda River in its North and Delhi -Amritsar railway line in the West of the town are major physical barriers. New grain market and sugar mill in the East and urban estate and other institutions in the South clearly show the trend of the development towards these two directions. Due to its location on National Highway number-44 (Earlier National Highway No.1), the area has under gone tremendous socio-economic and physical development. As a result into growth in population and infrastructure available like water, electricity, roads, communication and Tele communication, urban estate, the new urban estate has been planned. The people of all religious sections live there.

The town is situated on $30^{\circ}10'$ North latitudes and $76^{\circ}52'$ East longitudes. Originally the industrial activities in this town are agro based. The scenario will change radically as soon as the area is developed into an integrated township/urban centre of controlled area to be developed in the close vicinity of the town. The town is protected by a bandh and railway line from the flood of Markanda river.

The area is normally plain. Rain water flows to south-west direction. The land of this area is fertile and the ground water table is at 240 feets approximately potable water is very sweet.

II. Demographic profile:-

The existing abadi of Shahabad town falls within Municipal limit. The population of town was 42607 person in 2011. The decadal growth rate of population during 1961-1971 was 13.3% which increased to 22.36% in 1971-1981. However it reduced to as 19.55% in 1981-1991, 18.00% in 1991-2001 19.55% in 2001-2011 as given below:

Year	Population	Decennial % age
1951	17,301	-
1961	18,975	9.6%
1971	21,500	13.3%
1981	26,308	22.36%
1991	31,452	19.55%
2001	37,130	18.05%
2011	42,607+3018* =45625	22.88%

^{*}Population of Villages falling within the limits of urbanizable area.

III. Economic characteristics:-

The economic base of town and others villages falling in this controlled area is mainly agriculture. The main crops cultivated here are wheat, rice and maize. There are some retail shops, existing commercial centre and grain market running to meet the daily needs of the residents. In addition to this, small scale industries like Cold store, Rice Sheller, Flour Mill and Heavy Industry i.e. Sugar Mill, Vanaspati Mill and Fertilizers Mill exist in this area.

IV. Existing distribution of land uses, services, utility, facilities with environmental concern:-

(a) Utilities:-

- (i) Area falling residential zone is 105 hectares with population density 373 persons per hectare.
- (ii) Area falling commercial, Retail and Wholesale trade service area/ hinterland, tourism and Heritage is 64 hectares. There are a lot of retail shops, existing commercial centre and grain market, cold storage, Banquet Halls and Godown running to meet the daily needs of the residents. Hence the town is under development in commercial activities.
- (iii) Area falling under industries is 60 hectares, most of the industries exist along National Highway number-44 and Shahabad to Saha (Scheduled no. 78).
- (iv) Shahabad town is located on National Highway number-44 and broadgage electric railway line. Railway station and bus stand exists on railway line and National Highway number-1 respectively. Thus, this area is well linked with the other important towns of the State. The road/street within the town are almost narrow thesevaries from 6mtrs. to 14 mtrs. One telephone exchange is already working in the town. The Vechles are being park along the side of road / street. Area under transport and communication zone exists 71 hectares.
- (v) At present Electricity is located being supplied from 66 KV sub-station which is situated at National Highway number-44 and fulfills the present requirements. The water supply is provided from tubewells installed by Public Health Department. Sewerage system has been laid in existing urban estate. The open drains are constructed along streets in the existing town. Area under public utility zone falls 10 hectares.

(b) Social Infrastructure:-

- (i) There are three degree college, three senior secondary school, high school, primary schools and nursery schools to provide educational facilities. There are one University (Adesh Haryana University), one 70 bedded civil hospital along with number of private nursing homes, cilinics and veterinary hospital. There are dharamshalas for social gathering purposes in the town. There are Markandeshwar temple, Devi BalaSundri temple and Shakumbhri Devi temple. Area under public and semi public zone is 36 hectares.
- (ii) There is only park named Ch. Ranbir Singh Hooda. There is only one stadium in the town. There are two Shamshan Ghats/ Crematorium. There is a lack of open spaces / Parks in the town. Area under open space zone falls 28 hectares.

V. Need for declaration of Controlled Area:-

Keeping in view the urban growth of town in controlled area was declared under section-4(1)a of the Punjab Scheduled Roads and Controlled Areas Restriction of Unregulated Development Act, 1963 (Punjab Act 41 of 1963), vide notification No. 8028 VDP-70/6784, dated the 17th December 1970, published on 29th June, 1971 and development plan of this area was published in January 1973. Due to establishment of sugar mill, tehsil office, college and grain market etc, additional controlled area had been declared vide notification No.CCP(NCR)/KKR-CA-II/1620, dated the 18th September, 1998 published in Haryana Government Gazette, dated the 19thSeptember, 1998 besides controlled area pocket -1&II along National Highway Number. -1 (now National Highway Number 44) had been declared vide notification no CCP(NCR)/KKR/CA-ALNG NH-1/2009/3339, dated the 7th December 2009, published on 7th December, 2009.

VI. Planning proposals:-

Population Projection: Markanda river passes through the controlled area along the North-West side of existing town. This river is the natural barrier for the proposed planned development. The existing town has high potential regarding future development. Total controlled area of the proposal is 14271 hectares out of which 1116 hectares area has been proposed for urbanisable purposes.

The growth rate of population of town is moderate. The future population projection has been made at the average growth rate of 40% for decade 2011-2021 and 2021-2031 which comes out to be 82,000 and 1,46,000 persons respectively Keeping in view the huge demand of existing area and residential area of 105+470=575 hectares with gross density of 253 persons per hectare has been proposed in this plan to accommodate the population of 1,46,000 persons. as given below:-

Table-1

Year	Population	Decennial % age
2021	82,000	79.73%
2031	1,46,000	78.05%

Land uses:-

An area of 1116 hectares has been proposed as urbanisable area with the gross density of 96 persons per hectare. The town has been planned with the projected population of about 1,46,000 person for the perspective year 2031AD to meet the requirement of various socio-economic activities in the town, land is rationally marked for different land uses taking into account the nature of town inter linkages of town. The detailed breakup of the proposed land uses within the controlled area is as below:-

TABLE II

(Area in hectares)

Serial number	Land use	Area within municipal committee limit	Area within extended municipal committee limit	Area within controlled area	Total area	%age
1	Residential	-	444	60	504	45.16
2	Commercial	-	124	00	124	11.12
3	Industrial	-	48	48	96	8.60
4	Transport and Communication	-	97	46	143	12.81
5	Public Utilities	-	12	15	27	2.42
6	Public and semi Public	-	41	00	41	3.67
7	Open space/Green Belt	-	133	30	163	14.61
8	Special Zone	-	18	00	18	1.61
	Total		917	199	1116	100.00

Note: {Total Urbanisable area = 1490 hectares i.e.1116 hectares (urbanisable area planned) + 374 hectares (area under existing town)} Total controlled area Shahabad = 14271 hectares.

Description of land uses:-

1. Residential:-

An area measuring 504 hectares has been proposed in town under residential use to accommodate the project population of 1,46,000 persons by 2031AD. Sector No. 1 (Part), 3 (Part), 5, 6, 9 (Part), 10 (Part), 13 and 14 (Part) have been reserved for residential use. Every residential sector shall be developed to the sector density indicated in the drawing and in addition to it, the density as prescribed in the New Integrated Licensing Policy (NILP), Affordable Group Housing policy, DeenDayal Jan AwaasYojna Policy (DDJAY). 20% Group Housing component policy will also be applicable in a residential sector.

Apart from the above, following provisions has also been made in Development Plan:-

a. The additional area for infrastructure shall be provided in the already planned/developed residential sectors to meet out the requirement of the additional population.

b. The minimum width of the roads in a residential colony/sector shall not be less than 12 metres or as per applicable policies.

The minimum area for parks/open spaces in a residential colony/sector shall be planned in such a manner that it shall meet the minimum norm of 2.5 sq. metre per person

2. Commercial:-

The town having very fertile agriculture land hinterland and growing as local commercial center Therefore an area mearusing 124 hectares has been earmarked for commercial activities in Sector 3 (Part), 9 (Part), 12, 14 (Part).

3. Industrial:-

Main industries developing in this area is Rice Shallers. This type of industry needs a sizable area to operate. Therefore these are set up outside town /urbanisable area. A suitable provision for setting up such agro based industries in agriculture zone has been given in Annexure-B. There is a much scope for developing agro based/food processing industries to provide backward linkage with the hinterland. Therefore, an area measuring 96 hectares has also been earmarked for the industrial use in sector 7 (Part), 8 (Part) and 11(Part)to promote industrial activities. The wind flows from north-west to south-east direction. The Sugar mill already exists in the town.

4. Transport and Communication:-

National Highway No. 44 and Ladwa Scheduled road Number 69, Scheduled Road Number 57 Kala Amb-Sadhaura-Shahabad-Thol Road is passing through the town. A 30 meters wide green belt has been proposed along both sides of all schedules roads passing though the town. Since, the total urbanisable area 1116 hectare has been proposed. The sector dividing road is 45 meters wide. A 30 meters wide (V-3) with 30 mts. green belt has been proposed. The width of outer peripheral road has been proposed 45 mts wide with 30 mtr wide green belt. The area proposed under Transport and Communication Zone is 143 hectares which includes 62 hectares under roads and 81 hectares area earmarked in sector 4 and 11(part). The detail of various roads proposed in the development plan along with their road reservations is as under:-

Serial number.	Classification	Land reservation
(i)	V-1 National Highway Number 44 (Earlier National Highway Number 1)	Existing width with 30 meters green belt along both sides.
(ii)	V-1 (a) Road	45 meters wide peripheral ring road with 30 meters green belt along both sides.
(iii)	V-1(b) Road	Sector road 45 meters wide.
(iv)	V-2 Road	Existing scheduled road with 30 meters restricted belt along both sides
(v)	V-3 Road	30 meters wide sector road.
(vi)	V-4 Road	Existing sector road 30 meters wide

5. Public Utility Zone:-

A total area mearsuing 27 hectares has been earmarked for public utility zone which includes area for sewage disposal works, solid waste and space for electric power installations to cater to the additional needs the town.

6. Public and Semi Public Use Zone:-

To provide the educational, cultural, religious, institutional, medical and health facilities, an area measuring 41 hectares has been reserved in sector 2 (part), 10 (Part). College, Hospital, Working Women Hostel and Old Age Home in sector-10 (Part).

7. Open Space and Green Belt Zone:-

A 30 meter wide green belt is proposed on both sides of the existing National Highway number-44. An area measuring 163 hectares falls under this green belt and open space. 30 meter wide green belt has been proposed along both sides of proposed peripheral road.

8. Agriculture Zone:-

The remaining area surrounding the urbanization proposals, which is predominantly agricultural, is proposed to be reserved as agriculture zone. An agriculture zone, however, would not eliminate the essential building activities within this area, such as the extension of the existing village contiguous to abadi-deh, if undertaken under project approved or sponsored by Government, and ancillary facilities necessary for the maintenance and improvement of this rural area.

9. Special Zone:-

Due to location of town on National Highway number-44, an area measuring 18 hectare has been reserved in sector-2 (Part) for recreational, entertainment & commercial Activities (mix land use).

Zoning Regulations:-

The legal sanctity to the proposals regarding land use is being given to the effect by a set of zoning regulations (Annexure-B) which form a part of this development plan. These regulations will govern the change of land use and standards of development. They also very elaborately detail out allied and ancillary uses which will be permitted in the various major land uses and stipulate that all change of land use and development shall be in accordance with the details shown in the sector plan thereby ensuring the preparation of detailed sector plans for each sector to guide the development and enforce proper control.

Annexure-B

Governing use and development of land in the controlled area around Shahabad as shown in Drawing No. DTP (KK) 1160/2019, dated the 12th October, 2019.

I. General:-

- (1) These zoning regulations forming part of the Final Development Plan for the controlled areas around Shahabad shall be called zoning regulation of Final Development Plan for the controlled areas.
- (2) The requirements of these regulations shall extend to the whole of the area covered by the Final Development Plan and shall be in addition to the requirements of the Haryana Municipal Act, 1973 (24 of 1973) and Punjab Scheduled Roads and Controlled Areas Restriction of Unregulated Development Act, 1963 (Punjab Act 41 of 1963) and the rules framed there under.

II. Definitions: -

In these regulations:-

- (a) 'Agro based Industries' means an industrial unit, which uses food grains, fruits or Agro waste as raw-material:
- (b) 'Approved' means approved by the competent authority;
- (c) **'Building Code'** means, the Haryana Building Code 2017;
- (d) 'Building rules' means the rules contained in part VII of the rules;
- (e) **'Cyber City'** means self contained intelligent city with high quality of infrastructure, attractive surrounding and high speed communication access to be developed for nucleating the Information Technology concept and germination of medium and large software companies Information Technology Enabled services; wherein no manufacturing units may be allowed;
- (f) **'Cyber Park/Information Technology Park'** means an area developed exclusively for locating software development activities, and Information Technology Enabled services wherein no manufacturing of any kind (including assembling activities) shall be permitted;
- (g) **'Drawing'** means Drawing No. DTP (KK) 1160/2019, dated the 12th October, 2019.
- (h) **'Extensive Industry'** means an industry set up with the permission of the Government and in extensive, employing more than 100 workers and may use any kind of motive power of fuel provided they do not have any obnoxious features;
- (i) **'Farm House'** means a house constructed by the owner of a farm at his land for the purpose of:
 - (i) Dwelling unit, i.e. main use,
 - (ii) Farm shed i.e. Ancillary use.

Notes:-

- (1) The construction of the farm house shall be governed by the restrictions given under clause XIX regarding 'provision of farm houses outside adadi- deh in agricultural zone'.
- (2) 'Farm sheds' shall be governed by the restriction mentioned in clause XIX regarding building control and site specifications.
- (j) **'Floor Area Ratio (FAR)'** means a quotient obtained by dividing the multiple total covered area of all floors and hundred, by the area of plot i.e.

$$FAR = \frac{\text{total covered area}}{\text{plot area}} \times 100$$

For the purpose of calculating FAR, cantilevered permitted roof projections, lift room, mumty, balcony, basement or any floor if used for parking, services and storage, stilt area (unenclosed) proposed to be used for parking and pedestrian plaza only, open staircase (without mumty), terrace with or without access, fire staircase, atrium, water tank, open court yard of permitted size shall not be counted towards FAR:

Provided that area under shaft, chutes, lift well and staircase from stilt to next floor shall be counted towards FAR only at once on ground floor;

Provided further that in case the ventilation shaft area is more than 3 square metres, it shall not be counted in FAR:

- (k) **'Fuel Station'** means the fuel filling station providing retail supply of fuel for automobiles which shall include petrol pumps, CNG station, bio-fuels, charging station, battery providing stations etc;
- (l) **'Green Belt'** shall mean, strips of land along sector/arterial road shown in the development plan primarily meant for the widening of the sector/arterial road in future
- (m) **'Group Housing'** means a building designed and developed in the form of flats for residential purpose or any building ancillary to group housing;
- (n) **'Heavy Industry'** means an industry to be set up in public or semi public or private sector with the permission of the Government (the cost of plant machinery etc. as defined in the industrial policy of the Government);
- (o) 'Information Technology Industrial Units' means the categories of industries included in the Annexure to the Government of Haryana Information Technology Policy, 2000 and in Appendix-1 to this notification and/or, as may be defined by the Government of Haryana from time to time;
- (p) **'Ledge or Tand'** mean a shelf-like projection, supported in any manner whatsoever, except by means of vertical supports within a room itself but not having projection wider than one metres;
- (q) **'Light Industry'** means industry not likely to cause injurious or obnoxious noise, smoke, gas, fumes or odors, dust, effluent and any other nuisance to an excessive degree and motivated by electric power;
- (r) **'Local Service Industry'** means an industry, the manufacture and product of which is generally consumed within the local area, for example: bakeries, ice-cream manufacturing, aerated water, attachakkies with power, laundry, dry cleaning and dyeing repair and service of automobile, scooters and cycles, repair of household utensils, shoe making and repairing, fuel depots etc. provided no solid fuel is used by them.
- (s) **'Loft'**shall mean an intermediate space between two floors on a residual space with maximum height of 1.5 metres and which is constructed or adopted for storage purposes only;
- (t) **'Material Date',** 'material date' means the date of publication of notification of various controlled areas declared as under:

Serial number	Name of the controlled area and Notification No.	Material date
1.	Controlled area notified <i>vide</i> Haryana Government Gazette notification No. 8028 VDP-70/6784 dated 17th December 1970, published on 29th June, 1971	29.06.1971
2.	Additional Controlled Area notified <i>vide</i> Haryana Government Gazette notification No.CCP(NCR)/KKR-CA-II/1620, dated 18th September, 1998 published in Haryana Govt. Gazette on dated 19th September, 1998.	19.09.1998
3.	Controlled area pocket-I and pocket-II notified <i>vide</i> Haryana Government Gazette notification No. CCP(NCR)/KKR/CA-ALNG NH-1/2009/3339, dated 7thDecember 2009, published on 7thDecember, 2009	07.12.2009

- (u) 'Medium Industry' means all industries other than Light Industry and Local Service Industry and not omitting obnoxious or injurious fumes and odours;
- (v) **'Mezzanine floor'** means an intermediate floor, between two floors, with area restricted to ½ (half) of the area of the lower floor and with a minimum height of 2.3 metres and shall not be lower than 2.3 metres (clear height) above floor level;

- (w) 'Non-conforming use'in respect of any land or building in a controlled area means the existing use of such land or building which is contrary to the major land use specified for that part of the area in the Draft Development Plan.
- (x) 'Obnoxious or 'Hazardous Industry' means an industry set up with the permission of the Government and is highly capital intensive associated with such features as excessive smoke, noise, vibration, stench, unpleasant or injurious effluent, explosive, inflammable material etc. and other hazards to the health and safety of the community.
- (y) **'Public Utility Service Building'** means any building required for running of public utility services such as water supply, drainage, electricity, post and telegraph and transport and for any municipal service including a fire station.
- (z) 'Rules' the Rules framed under the Punjab Scheduled Roads and Controlled Areas Restriction of Unregulated Development Rules, 1965.
- (za) **'Sector Area'** and **'Colony Area'** shall means the area of sector or of colony indicated as such in the Development Plan;

Explanation:-

- (1) In this definition the 'Sector Area' or 'Colony Area' shall mean the area of the Sector or of Colony as shown on the drawing on the approved layout plan of the colony/sector which will be excluding the area unfit for building development within the sector or the colony as the case may be.
- (2) Benefit of 50% of the area falling under major roads and their adjoining green belts, if any, shall be allowed for plotable area/floor area ratio (FAR) in case of plotted/group housing colony;
- (3) In the layout plan of colony or sector, other than industrial colony/sector, the land reserved for roads, open space, schools, public and community building and other common uses shall not be less than 45% of the gross area of the land under the colony/sector;
- (4) For the purposes of calculation of sector density or colony density, it shall be assumed that 50 percent of the sector area or colony area will be available for residential plots including the area under Group Housing and that every building plot shall on the average contain three dwelling units each with a population of 4.5 persons per dwelling unit or 13.5 persons building plot or as incorporated in the zoning plan of the colony/group housing complex. In the case of shop-cumresidential plot, however, only one dwelling unit shall be assumed;
- (5) Notwithstanding above, the projects approved under specific policy like New Integrated Licensing Policy; Floor Area Ratio and density shall be the governing parameters instead of plotable area;
- (zb) 'Sector Density' and 'Colony Density' shall mean the number of persons per hectares in sector area or colony area or colony area as the case may be;
- (zc) **'Site Coverage'** means ratio expressed in percentage between the area covered by the ground floor of building and the area of the site;
- (zd) **'Small Scale Industries'** means Industrial unit, which is registered as Small Scale Industry by the Industries Department.
- (ze) **'Subservient to Agriculture'** mean development and activities, which are required to assist in carrying out the process of "agriculture" such as tubewells, pump chambers, wind mills, irrigation drains, pucca platform, fencing and boundary walls, water hydrants etc;
- (zf) The terms 'Act', 'Colony', 'Colonizer', 'Development Plan', 'Sector' and 'Sector Plan' shall have the same meaning as assigned to them in the Punjab Scheduled Roads and Controlled areas Restriction of Unregulated Development Act, 1963 (Punjab Act 41 of 1963) and rules, 1965 framed there under.
- (zg) Any other term shall have the same meaning as assigned to it in the Punjab Scheduled Roads and Controlled Areas Restriction of Unregulated Development Act, 1963, (Punjab Act 41 of 1963) and the rules 1965 framed there under:

III. Major land uses/zone :-

- 1. (i) Residential Zone
 - (ii) Commercial Zone
 - (iii) Industrial zone
 - (iv) Transport and Communications Zone

- (v) Public Utility Zone
- (vi) Public and Semi-Public Zone
- (vii) Open Spaces Zone.
- (viii) Agriculture Zone.
- (ix) Special Zone.
- 2. Classification of major land uses is according to Appendix 'A'.

IV. Division into sectors :-

Major land uses mentioned at serial number (i) to (viii) in zoning regulation-III above, which are land uses for building purposes, have been divided into sectors as shown on the concerned development plan drawing and each sector shall be designated by specific number as indicated on the drawing.

V. Detailed land uses within major uses :-

Main, ancillary and allied uses, which are subject to the other requirements of these regulations and of the rules, may be permitted in the respective major land uses zones are listed in Appendix-B sub-joined to these zoning regulations.

VI. Sector not ripe for development:-

Notwithstanding the reservation of various sectors for respective land uses for building purposes, the Director may not permit any changes in their land use or allow construction of building thereon from considerations of compact and economical development of the controlled area till such time as availability of water supply, drainage arrangement and other facilities for these sectors are ensured to his satisfaction.

VII. Sectors to be developed exclusively through Government enterprises:-

Government may notify any sector for development exclusively by it or by its agencies, in which case, no further permission for change of land use or grant of licence shall be permitted in such sectors.

VIII. Land reservation for major roads:-

(1) Land reservation for major roads marked in the Drawing shall be as under:

Serial number.	Classification	Land Reservation
(i)	V-1 National Highway No. 1 / No. 44	Existing width with 30 meters green belt along both sides.
(ii)	V-1 (a) Road	45 meters wide peripheral ring road with 30 meters green belt along both sides.
(iii)	V-1(b) Road	Sector road 45 meters wide.
(iv)	V-2 Road	Existing scheduled road with 30 meters restricted belt along both sides
(v)	V-3 Road	30 meters wide sector road.
(vi)	V-4 Road	Existing sector road 30 meters wide

- (2) Width and alignment of other roads shall be as per sector plans or as per approved layout plans of colonies.
- (3) Benefit of tradable Floor Area Ratio, may be allowed against licences granted for the land falling under sector road or green belt and open space zones in accordance with specified policies.

IX. Non-conforming uses either existing or having valid charges of land use permission:-

- 1. With regard to the existing industries shown in the zones other than industrial zone in the Development Plan, such industrial non-conforming uses shall be allowed to continue for a fixed period to be determined by the Director, but not exceeding ten years, provided that the owner of the building concerned:
 - (a) Undertakes to pay to the Director, as determined by him the proportionate charges toward the external development of the site as and when called upon by the Director to do so in this behalf;
 - (b) During the interim period makes satisfactory arrangement for discharge of effluent to the satisfaction of the Director.

- (c) Shall not be allowed to expand the existing project within the area of non-conforming use.
- 2. With regard to the projects having valid change of land use permissions, and located in the zones other than conforming use zone in the Development Plan, such non-conforming uses shall be allowed to continue, provided that the owner of the building concerned:
 - (a) Undertakes to pay to the Director, as determined by him the proportionate charges toward the external development of the site as and when called upon by the Director to do so in this behalf; and
 - (b) During the interim period makes satisfactory arrangement for discharge of effluent to the satisfaction of the Director.

X. Discontinuance of non-conforming uses:-

- 1. If a non-conforming use of land has remained discontinued continuously for a period of two years or more, it shall be deemed to have terminated and the land shall be allowed to be re-used or re-developed only according to the conforming use.
- 2. If a non-conforming use building is damaged to the extent of 50 percent or more of its re-production value by fire, flood, explosion, earthquake, war, riot or any other natural calamity, it shall be allowed to be re-developed only for a conforming use.
- 3. After the discontinuance of projects included under clauses IX, the land shall be allowed to be redeveloped or used only for conforming use.
- 4. After a lapse of period fixed under clause IX(1), the land shall be allowed to be re-developed or used only for conforming use.

XI. Development to conform to sector plan and zoning plan:-

Except as provide in regulation IX, no land within major land use shall be allowed to be used and developed for building purposes unless the proposed use and development is according to the details indicated in the sector plan and zoning plan or the approved colony plan in which the land is situated.

XII. Individual site to form part of approved layout or zoning plan:-

No permission for erection or re-erection of building on a plot shall be given unless-

- (i) The plot forms a part of an approved colony or the plot is in such area for which relaxation has been granted as provided in regulation XVII; and
- (ii) The plot is accessible through a road laid out and constructed up to the situation of the plot to the satisfaction of the Director.

XIII. Minimum size of plots for various types of buildings:-

(1) The minimum size of the plots for various types of uses shall be as below:-

Serial number	Land Use	Size				
i.	Residential plot	50 Square meters	59.8 square yard	538.20 square feet		
ii.	Residential plot on subsidized industrial housing or slum dwellers housing scheme approved by the Government	35 Square meters	41.86 square yard	376.74 square feet		
iii.	Shop-cum-residential plot	100 Square meters	119.60 square yard	1076.40 square feet		
iv.	Shopping booths including covered corridor or pavement in front	20 Square meters	23.92 square yard	215.28 square feet		
V.	Local service industry plot	100 Square meters	119.60 square yard	1076.40 square feet		
vi.	Light industry plot	250 Square meters	299 square yard	2691 square feet		
vii.	Medium industry plot	8000Square meters	9568 square yard	86112 square feet		

(2) The area norms for group housing colony, plotted residential colony and commercial colony shall be in the accordance with the policies specified from time to time for residential and commercial development. However, in a case group housing scheme is floated by Haryana Shehri Vikas Pradhikaran or any other Government Agency, the size of group housing site shall be as specified in the scheme.

XIV. Site coverage, height and bulk of building under various types of buildings:-

The site coverage, Floor Area Ratio and height permitted on a specific plot/site shall be governed by the prescribed policy parameters, building code/rules and /or as laid down in the zoning plan of such plot/site.

XV. Building lines in front and rear of building:-

These shall be provided in accordance with building code/rules and /or as laid down in the zoning plan of such site.

XVI. Architectural control:-

Wherever architectural control is considered necessary, every building shall conform to architectural control prepared as per clause 6.4 of Haryana Building Code 2017.

XVII. Relaxation of agricultural zone:-

In the case of any land lying in Agriculture zone, Government may relax the provisions of this development plan:-

- (a) for use and development of the land into a residential or industrial colony provided the colonizer has purchased the land for the said use and developed prior to the material date and the colonizer secures permission for this purpose as per Rules.
- (b) for use of land as in individual site (as distinct from an industrial colony).

Provided that:

- (i) the land was purchased prior to the material date;
- (ii) the Government is satisfied that the need of the industry is such that it cannot await alternative allotment in the proper zone;
- (iii) the owner of the land secures permission for building as required under the Rules;
- (iv) the owner of the land undertakes to pay to the Director, as determined by him, the proportionate charges as and when called upon by the Director in this behalf and during the interim period makes satisfactory arrangement for discharge of effluent.

Explanation: The word purchase in the regulation shall means acquisition of full property right and no lesser title, as agreement to purchase etc.

XVIII. Density:-

Every residential sector shall be developed to the sector density indicated in the drawing with 20% variation on either side and in addition to it, the density as prescribed in the New Integrated Licensing Policy, Deen Dayal Jan Awaas Yojna Policy and Affordable Group Housing Policy, 20% Group Housing component policy shall also be applicable in a residential sector.

XIX. Provision of farm house outside abadi- deh in agricultural zone:-

Farmhouses shall be allowed only for bonafide use of landowner(s) provided he does not own a house in any urban area because the real objective for allowing farmhouses in agriculture zone is to meet the housing needs of the farmers on a small portion of the farm so that he can take care of his agriculture produce while living on that farm. Hence, a farm house in agriculture zone, outside abadi-deh may be allowed if the area of the land is 2 acres or more on the following conditions:-

(i) Site Coverage	Size of farm house	Main building of the dwelling unit	Ancillary building of main dwelling unit
	2 Acres minimum but CLU permission for the area falling under road reservation /proposed road widening as per Development Plan, shall not be considered. However the net area should not be less than 1.5 acres after excluding the area falling under the green belt/ restricted belt and falling in Agriculture zone from applied area of 2 acres.	As applicable to residential plot equivalent to 250 square yards.	l percent of the farm land (not more than 40% shall be used for labour/servant quarters)

		Upto 3 acres	As applicable to residential plot equivalent to 375 square yards.	-do-
		Upto 4 acres and above	As applicable to residential plot equivalent to 500 square yards.	-do-
(ii)	Height and	Storey	11 metres, three storeyed	4 metres, single Storey.

(iii) Set back :-

It shall be at least 10 meters away from the edge of the agricultural land on all sides provided that if land attached to the farm house abuts a road, the house shall be constructed with a minimum set back from the edge of the road as under:

Serial Number	Road	Width
(a)	Where the road is bye pass to a Scheduled Road.	100 metres
(b)	Where the road is a Scheduled Road or as shown in the Development Plan.	30 metres
(c)	Any other road.	10 meters

(iv) Approach road :-

Any revenue rasta/road defined in the revenue record.

(v) Basement:-

Basement shall be permitted to the maximum extent of ground coverage and uses are permitted as per the Haryana Building Code-2017.

(vi) Ledge, Loft and Mezzanine floor:-

Ledge, Loft and Mezzanine floor shall be permitted within the building subject to the restrictions above as well as the restrictions stipulated in the definition given in clause –II of zoning regulations of Development Plan.

(vii) Service water supply and drainage:-

- (a) Good potable water supply should be available in the farm for human consumption in case of farm house is built.
- (b) Open sanitary drains or covered drains to be provided to clean the sheds in case of Dairy farms, Drains are to be provided for carrying rain water in case of all buildings.
- (c) Septic tank to be provided for disposal of human and animals waste as per provisions of the Rules.
- (d) The distance between the septic tank and open well or tubewell shall be as provided in the Rules.
- (viii) The owner shall be permitted to construct boundary wall around the main dwelling unit and ancillary portion thereof and around remaining area of farm barbed wire fencing shall be allowed.
- (ix) The CLU permissions for setting up of farmhouse shall be considered in the area other than over exploited or critical areas as declared by Central Ground Water Board.

Provided that Government may amend the minimum size of the farm for any scheme sponsored by the State Government/State Agency for the proper utilization of the agriculture zone.

XX. Provision of information technology units and cyber parks/cyber cities:-

(i) Location:-

- (a) Information Technology Industrial Units will be located in Industrial Areas/Industrial Zones only:
- (b) Cyber Parks/Information Technology Parks will be located either in Industrial Areas or Industrial zones abutting sector roads in the form of integrated development. However, no manufacturing units will be permitted in such parks.
- (c) Cyber Cities: The location of such a facility will be decided by the Government;

(ii) Size:-

Serial number	Туре	Size
1	Information Technology Industrial Unit	1 to 5 acres
2	Cyber Park/Information Technology Park	5 to 15 acres
3	Cyber City	Minimum 50 acres

(iii) Miscellaneous:-

(I) Parking:-

Parking will be as per the provisions of Haryana Building Code 2017 as amended from time to time.

(II) OtherActivities:-

- (a) Incidental commercial activities like Banks, Restaurants, Insurance Offices etc. shall be permitted subject to restriction of 4% of the gross area of the Cyber Park/Information Technology Park;
- (b) Only 5% of the area of the Cyber City shall be allowed for Group Housing and 4% of the total area of the Cyber City shall be permitted for Commercial/Institutional uses.
- (c) No residential plotted development shall be allowed in a Cyber City;
- (d) For a Cyber City Project if allowed in Agricultural Zone, the entrepreneur shall make the arrangement of water supply and other facilities like sewerage disposal/drainage etc;
- (III) The Government may impose any other condition as deemed necessary from time to time.

XXI. Setting up of communication towers:-

Permission of Mobile Towers within the Controlled area shall be granted as per the policy instructions of Department memo dated 10.03.2015 and as amended from time to time.

XXII. Safety against seismic hazards:-

As the Development Plan area falls in Zone III as per Seismic Zone map of Indian Standard IS 1893:2002 and hence is considered as High Risk Zone. In order to take care of the same "the whole urban development shall be checked for safety against intensity "VII" probability of occurrence, and upgraded for required seismic resistance in buildings and infrastructure as found necessary.

XXIII. Brick kilns in controlled areas :-

Sitting of the brick kilns in the Controlled Areas shall be governed by the respective policy/ guidelines issued by the Competent Authority from time to time.

XXIV. Relaxation of Development Plan:-

Government may in case of hardship or with a view to save any structure constructed before the material date, relax any of the provisions of the Development Plan on principles of equity and justice on payment of such development charges and on such other conditions as it may deem fit to impose.

Appendix-A

Classification of land uses

	1						
Main code	Sub code	Main group	Sub group				
100		Residential	Residential Sector on neighborhood pattern				
200		Commercial					
	210		Retail Trade				
	220		Wholesale Trade				
	230		Warehousing and Storage				
	240		Office and Banks including Government Office				
	250		Restaurants, Hotels and Transient Boarding Houses including public assistance institutions providing residential accommodation like Dharamshala, Tourist House etc.				

Main code	Sub code	Main group	Sub group
	260		Cinema and other places of public assembly on a commercial basis.
	270		Professional Establishments
300		Industrial	
	310		Service industry
	320		Light industry
	330		Extensive industry
400		Transport and Communication	
	410		Railway yards, railway station and sidings.
	420		Roads, Road Transport Depots and Parking Areas
	450		Telegraph offices, Telephone Exchanges etc
500		Public Utilities	
	510		Water Supply installation including treatment plants
	520		Drainage and Sanitary installation including disposal works
	530		Electric power plants substation etc.
	540		Gas Installation and Gas work.
	550		Solid Waste Management sites.
600		Public and semi public	
	610		Government Administrative Central Secretariat District Offices, Law Courts, Jails, Police Stations, Governors and President's Residence.
	620		Education, Cultural and Religious Institutions
	630		Medical and Health Institutions
	640		Cultural institution like Theatres, Opera Houses etc. of a predominantly non commercial nature
700		Open Spaces	
	710		Sports Grounds, Stadium and Play Grounds
	720		Parks
	730		Green Belts, Garden, Agro forestry/floriculture and other Recreational Uses.
	740		Cemetreies, crematories etc
	750		Fuel stations and Bus Queue shelters
	760		Water Bodies/lakes
800		Agricultural land	
	830		Land under staple crops
	850		Forest land.
	880		Land under water
	890		Dairy farming
900		Special Zone	Recreational, Entertainment, and Commercial activities (mix land use)

Appendix-B

The permissible activities given under main land uses shall be allowed in accordance with the policy/parameters approved by the Government and/or at sites as approved by the Competent Authority in the Sector/Colony/Scheme Plan.

I Residential zone :-

- (i) Residence
- (ii) Social community religious and recreational buildings
- (iii) Public utility buildings.
- (iv) Educational buildings and all types of school and college where necessary.
- (v) Health institutions.
- (vi) Cinemas
- (vii) Commercial and professional offices.
- (viii) Retail shops, dhabas and restaurants.
- (ix) Local service industries.
- (x) Fuel stations.
- (xi) Bus stops, tonga, taxi, scooter and auto/rickshaw stand.
- (xii) Nurseries and green houses.
- (xiii) Any other minor needs to ancillary to residential use.
- (xiv) Starred hotels.
- (xv) Clubs/community Centres.
- (xvi) Communication Towers.
- (xvii) Guest/Boarding Houses.
- (xviii) Any other use, which the Government may in public interest decide.

II Commercial zone :-

- (i) Retail Trade.
- (ii) Wholesale Trade.
- (iii) Warehouses and storages.
- (iv) Commercial offices and banks.
- (v) Restaurant and Transient Boarding Houses including public assistance institutions providing residential accommodation like Dharamshala, Tourist House etc.
- (vi) Cinemas, Hotels, Motels and other places of public assembly like theatres, club, Dramatic Club, etc. run on commercial basis.
- (vii) Professional establishments.
- (viii) Residences on the first and higher floors.
- (ix) Local service industry.
- (x) Public utility buildings.
- (xi) Fuel stations and service garages.
- (xii) Loading and unloading yards.
- (xiii) Parking spaces, bus stops, taxis, tonga and auto/rickshaw stand.
- (xiv) Town parks.
- (xv) Communication Towers.
- (xvi) Any other use which the Government in public interest may decide.

III Industrial zone :-

- (i) Light industry
- (ii) Medium industry
- (iii) Obnoxious and Hazardous Industry
- (iv) Heavy industry
- (v) Service industry
- (vi) Warehouse and storages
- (vii) Parking, loading and unloading area
- (viii) Truck stand/bus stops, taxi, tonga and auto/rickshaw stand

Public utility, community buildings, retail shops, banks, dhabas, restaurants, two/three/five star hotels (ix) and insurance offices subject to a maximum limit of 3 percent of the total area of the sector as under: -

Serial	Name of	Ar	ea	No. of	Commercial	nmercial Maximum		Approach
Number	Facility	Minimum	Maximum	facilities in a sector	component	Ground Coverage	Ratio	Road
1	Dhabas	500 Square meters	1000 Square meters	2	50 Square meters	40 %	0.40	Minimum 18 metres
2	Restaurants	1000 Square meters	2000 Square meters	2	10 %	30 %	1.50	Minimum 18 metres
3	Two/ Three Star Hotels	1.0 Acre	2.5 Acres	2	15 %	30 %	As per commercial policy	Minimum 24 metres
4	Five Star Hotels	2.5 Acres	4.0 Acres	1	15 %	30 %	As per commercial policy	Sector Dividing Road with the provision of a service road

- Fuel stations and service garages. (x)
- Liquid Petroleum Gas godowns permitted by the Director. (xi)
- Cyber Parks/Information Technology Parks/ Information Technology Industrial Units
- (xiii) Health Facilities like Hospital, Dispensary, Nursing Home and Clinic as under:

Serial	Name of	Area		No. of Residential		Maximum	Floor
Number	facility	Minimum	Maximum	facilities in a	component	ground	area
				sector		coverage	ratio
1	Hospital	2.5 Acres	5.0 Acres	1	15 %	33 %	1.00
2	Dispensary	1.0 Acre	1.5 Acres	1	15 %	33 %	1.00
3	Nursing Home	250 Square meters	500 Square meters	2	Nil	60 %	1.00
4	Clinic	250 Square meters	500 Square meters	2	Nil	60 %	1.00

- Industrial Colony with a minimum area of 15 acres. The area utilization shall be as per policy issued vide ACS, T&CP, Haryana, Chandigarh memo no. Misc.388/PA(RB)/2015/7/16/2006-2TCP dated 01.10.2015 as amended upto date.
- **Communication Towers**
- (xvi) Ready mix concrete plant, wet mix plants, hot mix plants
- (xvii) Weighing Bridge
- (xviii) Service Garage, Sale/Display Centre-cum-service garage as under:

Serial	Name of facility	Area (in acres)		Commercial	Maximum	Floor	Approach	Height
number		Minimum	Maximum	component	ground coverage	Area Ratio	Road	
1	Service Garage	0.5	1	Nil	60%	1.25	Minimum 18 metres or service road along sector road	18 metres
2	Sale/Display Centre-cum- service garage	0.5	2	10% of permissible Floor Area Ratio	60%	1.25	Minimum 18 metres or service road along sector road	18 metres

Note:* The fee and charges on commercial component shall be levied on the commercial rates;

- * Existing/already CLU granted service garages shall be considered for grant of permission for sale/display centre subject to fulfillment of the above norms.
 - (xix) Any other use, which the Government may, in public interest decide.

IV Transport and communication zone:-

- (i) Railway yards, railway station and siding.
- (ii) Transport Nagar, Roads and Transport depots and parking areas.
- (iii) Airports and Air Stations.
- (iv) Telephone exchange.
- (v) Broadcasting stations.
- (vi) Televisions station.
- (vii) Agricultural, horticulture and nurseries at approved sites and places.
- (viii) Fuel stations and service garages.
- (ix) Parking spaces, bus stop-shelters, taxi, Tonga and auto/ rickshaw stands.
- (x) Logistics Hubs/Container Yards, In land container Depot, Container Freight Station.
- (xi) Weighing Bridge.
- (xii) Communication Towers.
- (xiii) Warehouses upto a maximum limit of 20% of the total area of the sector.
- (xiv) Dhabas, as per prevailing policy.

V Public utilities :-

- (i) Water supply installations including treatment plants.
- (ii) Drainage and Sanitary installations including sewage treatment plants and disposal works.
- (iii) Electric Power plant and sub-station including grid sub-station.
- (iv) Gas installations and Gas works.
- (v) Solid Waste management Sites.

VI Public and semi public uses zone :-

- (i) Government offices, Government Administration centres, secretariats and police station.
- (ii) Educational, cultural and religious institutions.
- (iii) Medical health institutions.
- (iv) Civic/cultural and social institutions like theatres, opera houses etc. of predominantly non-commercial nature
- (v) Land belonging to defence.
- (vi) Dhabas, Restaurants as under: -

Serial	Name of		Area	No. of	Commercial	Maximum	Floor
number	Facility	Minimum	Maximum	facilities in	component	Ground	Area
				a sector		Coverage	Ratio
1	Dhabas	500 Squa	e 1000 Square	2	50 Square meters	50 %	50 %
		meters	meters				
2	Restaurants	1000 Squa	e 2000 Square	2	10 %	30 %	150 %
		meters	meters				

- (vii) Communication Towers.
- (viii) Fuel Stations.
- (ix) Any other use which Government in public interest may decide.

VII Open spaces :-

- (i) Sports ground, stadium and play grounds.
- (ii) Parks and green belts, garden and other recreational uses.
- (iii) Cemetreies, crematories etc.
- (iv) Fuel stations, bus queue shelter along roads with the permission of Director.
- (v) Public utility services like electric grid station, transmission lines, communication lines, water supply lines, sewerage lines, drainage lines in the green belts along the scheduled roads and major roads.
- (vi) Water bodies/ Lakes/water recharge zone.

- (vii) Communication Towers.
- (viii) Mela Ground and Multipurpose Ground.
- (ix) Any other use, which the Government may in Public interest decide.

VIII Agriculture zone :-

- (i) Agricultural, Horticultural, dairy and poultry farming.
- (ii) Village houses within Abadi-deh.
- (iii) Farm houses outside abadi-deh subject to restriction as laid down in zoning regulation XIX.
- (iv) Afforestation development of any of the part for recreation.
- (v) Expansion of existing village contiguous to abadi-deh if undertaken as a project approved or sponsored by the Central Government, or State Government.
- (vi) Milk chilling station and pasteurisation plant.
- (vii) Bus Stand and railway station.
- (viii) Air ports with necessary buildings.
- (ix) Wireless stations.
- (x) Grain godowns, storage space at sites approved by the Director.
- (xi) Weather stations.
- (xii) Land drainage and irrigation, hydroelectric works and tubewell for irrigation.
- (xiii) Telephone and electric transmission lines and poles.
- (xiv) Mining and extraction operations including lime and brick kilns, stones, quarries and crushing subject to the rules and at approved site.
- (xv) Cremation and burial grounds.
- (xvi) Fuel stations and service garages.
- (xvii) Renewable and non-renewable energy power plants.
- (xviii) Liquid Petroleum Gas storage godowns with the approval of the Director.
- (xix) Small Scale Industrial units shall be allowed subject to fulfillment of the following conditions, provided that the site should not fall within restricted belt notified under the 'Works Defence Act, 1903' around Defence installations, if any:

A. Siting norms	A. Siting norms								
Zone	Norms								
Low potential zone	Within 2 kms from Urbanisable Zone (excluding the peripheral roads, if proposed along urbansiable boundary)	Beyond 2 kms from Urbanisable Zone (excluding the peripheral roads, if proposed along urbansiable boundary)							
	Non-polluting green category units of any area	Green and orange category units of any area							
B. Approach no	orms								
Medium & Low Potential zone	8								

(xx) Non polluting Medium and Large Scale Agro-based Industries on Public road/rasta not less than 30 feet wide other than scheduled roads, National Highway and State Highway subject to the condition that site should not fall within restricted belt around the defence installation as applicable for such installation if

any.

(xxi) Dhabas, Banquet Hall, Small Restaurants, Motels, Hotels, Resort and Amusement Park/ Theme Park along National Highway / Scheduled Roads in the area outside restricted/ green belt as under:

	Permissible Activity	Arc	ea	Commercial	Maximum	Floor Area	
number		Minimum	Maximum	Component	Ground Coverage	Ratio	
1	Dhabas	1000 Square meters	1 acre	50 Square meters	40%	40%	
2	Restaurant	2000 Square meters	1 acre	15%	30%	150%	
3	Motel with banquet facilities	2.5 acres	5 acres	15%	30%	150%	
4	Resort	4 acres	10 acres	15%	30%	150%	
5	Amusement Park/Theme Park	2.5 acres	10 acres	15%	30%	50%	

Provided the access permission is obtained from National Highway Authority of India if the site is located on National Highway, and from Executive Engineer, Public Works Department (Building and Roads) if the site is located on scheduled road.

(xxii) Banquet Hall:-

Permissible Zone	Agriculture Zone			
Approach	1. Minimum width of the approach road must be 18 meters			
	2. The access permission is required from XEN, PWD (B&R) if the site is located on scheduled road.			
	3. Approach from National Highways can be considered, if the site fulfills minimum distance norm from intersection/access and is located on minimum 7 meters wide service road or the applicant submits prior permission of access from NHAI			
Area Required	Minimum area 2.5 acres			
	Maximum area 5.00 acres			
Floor Area Ratio	50%			
Ground Coverage	30%			
Conversion Charges	50% of the rates prescribed for Commercial use			
Permissible Ancillary uses within Floor Area Ratio	10% of the allowed FAR for Gift Shop, STD Booth, Toy Centre and Flower Shops etc.			
Parking	Minimum 25% of the site area.			

Note: The provision of marriage palace/Banquet Hall within the Municipal Limit shall be as per the policy approved by the Department of Urban Local Bodies and as amended from time to time.

- (xxiii) Microwave Towers/Stations, Seismic Centers and Telecommunication Centers
- (xxiv) Communication Towers.
- (xxv) Ready mix concrete Plants, Wet Mix Plants, Hot Mix Plants connected with the projects for which contract or work is assigned by Government or Government agency and to be set up on short term basis.

(xxvi) Service Garage, Sale/Display Centre-cum-service garage as under:

Serial number	Name of facility	Area (in acres)		Commercial	Maximum	Floor	Approach	Height
		Minimum	Maximum	component	ground coverage	Area Ratio	Road	
1	Service Garage	0.5	1	Nil	60%	1.25	Minimum 18 metres or service road along sector road	18 metres
2	Sale/Display Centre-cum- service garage	0.5	2	10% of permissible Floor Area Ratio	60%	1.25	Minimum 18 metres or service road along sector road	18 metres

Note: * The fee and charges on commercial component shall be levied on the commercial rates;

(xxvii) Weighing Bridge.

(xxviii) Any other use, which Government may in Public Interest, decides.

IX Special Zone:-

Recreational, Entertainment, and Commercial activities (mix land use)

X Uses Strictly Prohibited:-

Storage of Petroleum and other inflammable material without proper license.

^{*} Existing/already CLU granted service garages shall be considered for grant of permission for sale/display centre subject to fulfillment of the above norms.

Appendix-1

Categories of Industries included in the scope / definition of Information Technology Industry

(A) Computing Devices including

Desktop

Personal Computer

Servers

Work-station

Nodes

Terminals

Network P.C

Home P.C.

Lap-top Computers

Note Book Computers

Palm top Computer/PDA

(B) Network Controller Card/ Memories including

Network Interface Card (NIC)

Adaptor Ethernet /PCI/EISA/Combo/PCMICA

SIMMs Memory

DIMMs Memory

Central Processing Unit (CPU)

Controller SCSI/Array

Processors Processor/Processor Power Module/Upgrade

(C) Storage Units including

Hard Disk Drives/Hard Drives

RAID Devices and their Controllers

Floppy Disk Drives

C.D. ROM Drives

Tape Drives DLT Drives/DAT

Optical Disk Drives

Other Digital Storage Devices

(D) Other

Key Board

Monitor

Mouse

Multi-media Kits

(E) Printers and Output Devices including

Dot matrix

Laserjet

Inkjet

Deskjet

LED Printers

Line Printers

Plotters

Pass-book Printers

(F) Networking products including

Hubs

Routers

Switches

Concentrators

Trans-receivers

(G) Software including

Application Software

Operating system

Middleware/Firmware

(H) Power supplies to Computer Systems including

Switch Mode Power Supplies

Uninterrupted Power supplies

(I) Networking/Cabling and related accessories

(related to IT Industry)

Fibre Cable

Copper Cable

Cables

Connectors, Terminal Blocks

Jack Panels, Patch Cord

Mounting Cord/Wiring Blocks

Surface Mount Boxes

(J) Consumables including

C.D.ROM/Compact Disk

Floppy Disk

Tapes DAT/DLT

Ribbons

Toners

Inkjet Cartridges

Inks for Output devices

(K) Electronic Components

Printed Circuit Board/Populated PCB

Printed Circuit Board/PCB

Transistors

Integrated Circuits/ICs

Diodes/Thyristor/LED

Resistors

Capacitors

Switches (On/Off, Push button, Rocker, etc.)

Plugs/sockets/relays

Magnetic heads, Print heads

Connectors

Microphones/Speakers

Fuses

(L) Telecommunication Equipment including:

Telephones

Videophones

Fascimile machines/Fax cards

Tele-Printers/Telex machine

PABX/EPABX/ RAX/MAX Telephone Exchange

Multiplexers/Muxes

Modems

Telephone answering machines

Telecommunication Switching Apparatus

Anetna and Mast

Wireless datacom equipment

Receiving equipments like Pagers, mobile/Cellular Phones, etc.

VSATs

Video Conferencing Equipments

* Including Set Top Boxes for both Video and Digital Signaling.

(M) IT Enabled Services are business processes and services, the end products/services of which are:-

- Delivered outside India.
- Delivered over communication network., and
- Either externally contracted (out-sourced) or provided by a remote subsidiary of the same company (out-located).

Note: Services which would not be included are:-

Remote production/manufacturing units


The Corporate offices of companies or their local branches

Virtual business on Internet.

The following services which meet the above criteria would be included:-

- (i) Back-Office Operations
- (ii) Call Centres
- (iii) Content Development or Animation
- (iv) Data Processing
- (v) Engineering and Design
- (vi) Geographic Information System Services
- (vii) Human Resource Services
- (viii) Insurance Claim Processing
- (ix) Legal Database
- (x) Medical Transcription
- (xi) Payroll
- (xii) Remote Maintenance
- (xiii) Revenue Accounting
- (xiv) Supports Centres and
- (xv) Web-site Services.

S. N. ROY, Additional Chief Secretary to Government Haryana, Urban Local Bodies Department. A.K. SINGH, Principal Secretary to Government Haryana, Town and Country Planning Department.



8793—C.S.—H.G.P. Pkl.